The Phase III Expansion of the White Street Sanitary Landfill

Greensboro, North Carolina

Construction Permit Application



November 1995

Prepared by:

HDR Engineering, Inc. of North Carolina 128 S. Tryon Street, Suite 1400 Charlotte, NC 28202-5001



HDR Engineering, Inc. of North Carolina

- .

.

.

•

.

TABLE OF CONTENTS

DIVISION 2 - SITE WORK

02220 EARTHWORK

02221 TRENCHING, BACKFILLING AND COMPACTING

02240 OPERATIONAL COVER AND LEACHATE COLLECTION LAYER

02276 SOIL LINER SYSTEM

02485 SEEDING

02515 HDPE MANHOLE STRUCTURES

02775 HDPE GEOMEMBRANE LINER SYSTEM

02800 GEOSYNTHETIC CLAY LINER (GCL)

02900 GEOTEXTILE FABRIC

02999 GEOCOMPOSITE DRAINAGE LAYER

DIVISION 3 - CONCRETE

03002 CONCRETE

.03431 PRECAST CONCRETE

DIVISION 15 - MECHANICAL

15060 PIPE AND PIPE FITTINGS: GENERAL

15064 PIPE: PLASTIC

15066 PIPE: STAINLESS STEEL

15069 PIPE: REINFORCED CONCRETE

15103 BUTTERFLY VALVES

15900 PIPE - CORRUGATED METAL



01		SECTION 02220	01
02 03 04		EARTHWORK	02 03 04
05 06 07	PART 1	- GENERAL	05 06
07 08 09	1.01	DESCRIPTION	07 08
10 11 12	Α.	Section Includes: 1. Earthwork.	09 10 11 12
13 14 15 16 17 18	В.	 Related Sections include but are not necessarily limited to: 1. Division 0 - Bidding Requirements, Contract Forms, and Condition of the Contract. 2. Division 1 - General Requirements. 3. Section 02276 Soil Liner System. 4. Accompanying CQA Plan. 	13 14 15 16 17 18 19
20 21 22 23 24 25 26 27 28 29 30	С.	 Definitions: Borrow: shall consist of approved material required for the construction of embankments/fills or for other portions of the work and shall be obtained from on-site areas designated on the plans unless directed otherwise by the Project Manager. Embankment and Fill: shall include construction of all site earthwork including roadways, landfill area, perimeter berm embankments, including preparation of the areas upon which materials are to be placed. All embankment and fill materials may be either (off-site) Select Borrow or (on-site) Borrow unless otherwise noted on drawings or specified by the Project 	20 21 22 23 24 25 26 27 28 29 30
31 32 33 34 35 36 37 38 39		Manager. 3. Unsuitable Material: is any in-place or excavated material which contains undesirable materials, or is in a state which is not appropriate; in the opinion of the CQA Consultant, for the intended use or support of planned structures, embankment, or excavation. This may include but not be limited to organic material, soft, or materials not meeting required specifications, etc.	31 32 33 34 35 36 37 38 39
40 41	1.02	QUALITY ASSURANCE	40 41
42 43 44 45	Α.	Perform all work in accordance with requirements of local and state codes, with requirements of OSHA, and in accord with federal requirements.	42 43 44 45
46 47 48 49 50 51 52 53	В.	Refer to the following standard references or specifications as applicable to this Section of Technical Specifications: 1. North Carolina State Building Code, Latest Edition. 2. North Carolina Erosion and Sediment Control Planning and Design Manual, Latest Edition. 3. North Carolina Department of Transportation Standard Specifications for Roads and Structures, Latest Edition. 4. American Society for Testing Materials (ASTM).	46 47 48 49 50 51 52 53

tions and testing to determine availability of (on-site) borrow

```
01
           materials, as allowed by the Owner.
01
                                                                                    02
02
                                                                                    03
03
                                                                                    04
    PART 3 - EXECUTION
04
                                                                                    05
05
                                                                                    06
    3.01 PROTECTION
06
                                                                                    07
07
           Protect existing surface and subsurface features on-site and
                                                                                    08
80
                                                                                    09
            adjacent to site as follows:
09
               Provide barricades, coverings, or other types of protection
                                                                                    10
10
                necessary to prevent damage to existing items indicated to
                                                                                    11
11
                                                                                    12
                remain in place.
12
                                                                                    13
            2. Protect and maintain bench marks, monuments or other estab-
13
                lished reference points and property corners. If disturbed or
                                                                                    14
14
                destroyed, replace at own expense to full satisfaction of Owner
                                                                                    15
15
                                                                                    16
                and controlling agency.
16
                Verify location of utilities. Omission or inclusion of utility
                                                                                    17
17
            3.
                items does not constitute non-existence or definite location.
                                                                                    18
18
                Secure and examine local utility records for location data.
                                                                                    19
19
                    Take necessary precautions to protect existing utilities
                                                                                    20
20
                                                                                    21
                    from damage due to any construction activity.
21
                                                                                    22
                    Repair damages to utility items at own expense.
22
                                                                                    23
                    In case of damage, notify Engineer at once so required
 23
                                                                                    24
                    protective measures may be taken.
 24
                Maintain free of damage, existing sidewalks, structures, and
                                                                                    25
 25
                pavement, not indicated to be removed. Any item known or
                                                                                    26
 26
                                                                                    27
                unknown or not properly located that is inadvertently damaged
 27
                shall be repaired to original condition. All repairs to be
                                                                                     28
 28
                                                                                     29
                made and paid for by Contractor.
 29
                Provide full access to public and private premises, fire
                                                                                     30
 30
                                                                                     31
                hydrants, street crossings, sidewalks and other points as
 31
                designated by Owner to prevent serious interruption of travel.
                                                                                     32
 32
                                                                                     33
                Maintain stockpiles and excavations in such a manner to prevent
 33
                                                                                     34
                 inconvenience or damage to structures on-site or on adjoining
 34
                                                                                     35
 35
                Avoid surcharge or excavation procedures which can result in
                                                                                     36
 36
                                                                                     37
                 heaving, caving, or slides.
 37
                 Conduct operation with minimum interference to daily landfill
                                                                                     38
 38
                                                                                     39
                 operations.
 39
                                                                                     40
 40
             Construction erosion and sedimentation controls prior to beginning
                                                                                     41
         Β.
 41
                                                                                     42
             earthwork.
 42
                                                                                     43
 43
             Dispose of waste materials, legally. Burning, as a means of waste
                                                                                     44
 44
         С.
                                                                                     45
             disposal, is not permitted.
 45
                                                                                     46
 46
                                                                                     47
      3.02 SITE EXCAVATION AND GRADING
 47
                                                                                     48
  48
             The work includes all operations in connection with excavation,
                                                                                     49
  49
         Α.
             borrow, construction of fills and embankments, rough grading, and
                                                                                     50
  50
             disposal of excess materials in connection with the preparation of
                                                                                     51
  51
                                                                                     52
             the site(s) for construction of the proposed facilities.
  52
                                                                                      53
```

Excavation and Grading: Perform as required by the Contract Drawings. Contract Drawings may indicate both existing grade and finished grade required for construction of Project. Stake all units, structures, piping, roads, parking areas and walks and establish their elevations. Perform other layout work required. property corner markers to original location if disturbed or destroyed. Preparation of ground surface for embankments or fills: Before 2. fill is started, scarify to a minimum depth of 6 IN in all proposed embankment and fill areas. Where ground surface is steeper than one vertical to four horizontal, plow surface in a manner to bench and break up surface so that fill material will bind with existing surface. Protection of finish grade: During construction, shape and drain embankment and excavations. Maintain ditches and drains to provide drainage at all times. Protect graded areas against action of elements prior to acceptance of work. Reestablish grade where settlement or erosion occurs. Borrow: Provide necessary amount of approved fill compacted to density equal to that indicated in this Specification. cost of all borrow material in original proposal. Fill material to be approved by Soils Engineer prior to placement. Construct embankments and fills as required by the Contract D. £ Drawings: ---Construct embankments and fills at locations and to lines of grade indicated. Completed fill shall correspond to shape of typical cross section or contour indicated regardless of method used to show shape, size, and extent of line and grade of 44.5 completed work. Provide approved fill material which is free from roots, organic matter, trash, frozen material, and stones having maximum dimension greater than 6 IN. Ensure that stones larger than 4 IN are not placed in upper 6 IN of fill or embankment. place material in layers greater than 8 IN loose thickness. Place layers horizontally and compact each layer prior to placing 38 additional fill. Compact by sheepsfoot, pneumatic rollers, vibrators, or by other equipment as required to obtain specified density. Refer to Table A for testing frequencies. Control moisture for each layer necessary to meet requirements of compaction. Upon reaching subgrade elevations shown, proofroll subgrade soils and obtain the CQC Agency's and CQA Consultant's approval. unsuitable materials are encountered at the subgrade elevation, perform additional excavation as directed by the CQC Agency and reviewed by the CQA Consultant to remove unsuitable materials.

Excavation of 1 CY or greater should be preapproved by the CQA

Consultant.


		Acceptance or Rejection Criteria	1. NCDOT No. 78M	2. As per Section 02221, paragraph 3.05C.	1. Meet Select Borrow/ Borrow as Per 2.01 A.	2. None.	3.A. 95% maximum density (Standard Proctor; 2%± Opt. Moisture except under Foundations/ Structures 98% Standard Proctor.	3.B. 75% Relative Density	
TABLE A	Minimum Testing Frequency for Soil Materials (Refer to CQA/CQC Plan for Methods)	Minimum Sample Frequency/Location	1. 1 Per Source	2. 1/Area Judged Unsuitable	1. 1 Per Source	2. 2 Per Soil Type/Source	3. I Per 10,000 S.F. Per Lift	And the second s	
17	Minimum Testing Freq (Refer to CQA/C	Required Test	1. Particle Size	2. In-place Density	1. Classification	2. Standard Proctor Density or Relative Density	3. In-Place Density A. Cohesive Soil	B. Granular Soil	
		Components	3 1	Areas (Granular)	Structural/Controlled				

- F. Proofrolling shall be conducted with a pneumatic tired vehicle of at least 20 tons GVW, approved by the CQA Consultant. An alternate approved by the CQA Consultant may be used in constricted areas.
- G. Where subgrade materials are determined to be unsuitable, such materials shall be removed to the lengths, widths and depths directed by the CQC Agency and approved by the CQA Consultant and backfilled with suitable material unless further excavation or earthwork is required. No additional payment will be made for such excavation and backfill 2 feet or less than the finished subgrade. Unsuitable material excavation greater than 2 feet beneath the finished subgrade shall be made on a unit price basis for excavation and backfill, only as approved by the CQA Consultant and Project Manager. Unit price for overexcavation and backfill greater than 2 feet in depth shall include disposal of unsuitable materials.
- H. The subgrade of areas to receive fill shall be smooth and free of all vegetation, sticks, roots, rocks and debris.
- Dewatering: Provide and maintain dewatering of all surface water and/or groundwater as required for excavation. Where groundwater is or is expected to be encountered during excavation, install a dewatering system to prevent softening and disturbance of subgrade below foundations and fill material, to allow foundations, fill material, and structures/backfill to be placed in the dry, and maintain a stable excavation. Groundwater shall be maintained at least 4 feet below the bottom of any excavation. Soils and hydrogeologic information may be reviewed before beginning excavation to determine where groundwater is likely to be encountered during excavation. Employ a dewatering specialist for selecting/designing, monitoring and operating the dewatering system as needed. Keep dewatering system in operation until dead load of structure exceeds possible buoyant uplift force on structure or fill material. Dispose of groundwater to an area which will not interfere with construction operations or damage existing construction as approved by the Owner. Install groundwater monitoring points as necessary. Shut off dewatering system at such a rate so as to prevent a quick upsurge of water that might weaken the subgrade. Installation, start-up, monitoring maintenance, and shut-off of the dewatering system shall be at no additional cost to the Owner.
- J. Do not place fill when the subgrade to receive fill is frozen, wet loose or soft.

K. Moisture control:

- 1. Moisture content of materials prior to, and during compaction, shall be uniform throughout each layer of material.
- 2. Granular materials shall be thoroughly wetted during or immediately prior to compaction.
- 3. Supplementary water shall be added as required to materials by sprinkling and mixing uniformly throughout layer.
- 4. Materials too wet for placing shall be temporarily spread or

aerated until moisture content is acceptable. If these materials cannot be processed in time to use, the Contractor shall find alternatives acceptable to the CQC Agency and the COA Consultant. 3.03 ROCK EXCAVATION All rock excavation shall be under one classification. This classification shall include solid ledge rock in its natural location that requires systematic quarrying, drilling and/or splitting for its removal and also boulders that exceed 1/2 CY 11. in volume. Rock is defined as natural material that cannot be ripped with a D-9 bulldozer or similar equipment. When rock is encountered immediately notify Engineer. Strip free of earth. Employ an independent surveyor to determine rock quantities before removal operation begins. In computing the volumetric content of rock excavation for payment, the pay lines ·18 shall be taken as follows: For structures: 3 FT outside the exterior limits of foundations and from rock surface to 6 IN below bottom of foundations. For piping and utilities: A width 18 IN wider than the outside diameter of the pipe or conduit and from rock surface to 6 IN below bottom exterior surface of the pipe or conduit. For paving: 2 FT outside the exterior limits of paving and from rock surface to 6 IN below bottom of pavement subbase. For landfill unit: 5 FT below subgrade and from rock surface. 3.04 METHOD OF REMOVAL AND PAYMENT Method of removal to be coordinated during construction. Payment terms to be negotiated at time of identification of rock. FINISH GRADING 3.05 Grade all areas disturbed by construction operations. Α. Grade to smooth, uniformly sloping surfaces to existing elevations or to finish elevations shown on drawings. Grading shall be to a tolerance of 2 IN (plus/minus) unless otherwise noted elsewhere in these specifications or in the accompanying CQA/CQC Plan. GRADING ADJACENT TO STRUCTURES 3.06 Evenly slope finished grade away from structures as shown on drawings to provide drainage. 3.07 FIELD QUALITY CONTROL



01		SECTION 02221					
02 03 04		TRENCHING, BACKFILLING AND COMPACTING	02 03 04				
05 06	PART 1	- GENERAL	05 06 07				
07 08 09	1.01	DESCRIPTION	07 08 09				
10 11 12 13 14 15	Α.	 General: Furnish all labor, materials, tools, equipment and services for excavation, trenching, backfilling and compacting for all utilities, culverts, pipes, manholes, etc. as indicated, in accord with provisions of Contract Documents. Completely coordinate with work of all other trades. 	10 11 12 13 14 15				
17 18 19 20 21	В.	Work included in the project consists of, but is not limited to, methods of installation of the following: 1. Surface drainage culverts and piping. 2. Leachate gravity header piping outside lined areas.	17 18 19 20 21				
22	С.	Related Work Specified	22				
23 24		1. Section 02220: Earthwork.	23 24				
25 26		2. Section 02276: Soil Liner System.	25 26				
27 28	e	3. Section 02775: Geosynthetic Liner System.	27 28				
29 30 31	1.02	QUALITY ASSURANCE	30				
32 33	Α.	Referenced Standards.	31				
34		1. American Society for Testing and Materials (ASTM)	33				
35 36 37 38 39 40 41	,	C33 Concrete Aggregates D2049 Relative Density for Cohesionless Soils D2487 Classification of Soils for Engineering Purposes D698 The Moisture-Density Relations of Soils using a 5.5-pound Rammer and a 12 IN drop	35 36 37 38 39 40 41				
42 43 44 45	В.	Contractor shall perform all required horizontal and vertical layout work. Such work shall be performed by a qualified surveyor or engineer.	42 43 44				
46	С.	Refer to the accompanying CQA Plan.	45				
47 48	1.03	SUBMITTALS	47				
49 50	Α.	See Section 01340.	4 <u>9</u>				
51 52 53	В.	Submit test reports and fully document each with specific location or stationing information, date, and other pertinent information.	51 52 53				

compliance with methods prescribed in these specifications.

01 02 03		3. Other granular material may be accepted by the Project 0 Manager or CQA Consultant. 0
04 05 06 07 08 09 10 11 12 13 14 15	PART 3	- EXECUTION 0
	3.01	GENERAL 0
	Α.	Remove and dispose of unsuitable materials at an approved site. 0
	B.	Excavate trench, backfill and compact for all underground pipe 1 lines, structures, bases and appurtenant items. 1
	С.	Provide dewatering as required for maintaining stable subgrade and for pipe installation.
16 17	3.02	EXCAVATION 1
1890123456789012345678901234544444444444444444444444444444444444	Α.	Excavation for appurtenances: 1. Excavate for appurtenant structures to provide at least 12 IN (minimum) clear distance between outer surface and embankment and in full observation to Safety Rules.
	B.	and in full observation to Safety Rules. 2 2 2 2 2 2 3 2 3 3 4 2 2 3 3 3 4 3 3 4 3 3 4 3 4
49 50 51		Overall Diameter of Utility Service Excess Dimension 4 ====================================
52 53		5 More than 33 IN 24 IN 5

01 02 03 04	3.05	COMPACTION	MINIMUM COMPACTIONS		01 02 03 04			
05 06 07 08 09 10 11 12 13 14 15 16 17 18 19 20 21		LOCATION	SOIL TYPE	DENSITY	05 06			
		All applicable areas	Cohesive soils	95 percent of max dry density by ASTM D698	07 08 09 10 11			
			Cohesionless soils	75 percent of max relative density by ASTM D4253 and D4254	12 13 14 15 16			
	Α.	A. Relative density of predominantly granular bedding or backfill ma be accepted by the CQC Agency (and approved by the CQA Consultant based on visual inspection without relative density testing, as deemed appropriate by CQA Consultant.						
22	3.06	FIELD QUALITY CONTROL						
23 24 25 26 27 28 29 31 33 34 35 36 37 38 40		and density tests backfill complies "Passing" tests s compaction does r after backfill ha and situation cor until compaction solely by Contrac shall be paid by 2. Ensure Owner has results of all so a safe condition 3. Demonstrate compa lift per 1,000 li	s as required to ensure with specified requishall be paid by Owner not meet moisture densus been removed as directed, additional temeets or exceeds requitor. Costs associated Contractor. at all times immediated in the contractor of the contractor	the where backfill sity test requirements and rected by the CQC Agency ests shall be performed airements with cost borned with "Failing" tests access to the test asure excavations are in frequency of 1 test per	23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39			
41 42	В.	Ensure full compliance	ce to applicable requi	rements of OSHA.	41 42			
43 44 45 46	С.	C. Special attention is directed to Title 29 Labor, Part 1518 - "Safety and Health Regulations for Construction" and detailed requirements of Subpart P "Excavations, Trenching and Shoring."						
47 48		ENI	O OF SECTION		47 48			

01			01
02 03 04		SEEDING (02 03 04
05 06	PART 1	I - GENERAL	05 06
07 08 09	1.01	DESCRIPTION	07 08 09
10 11 12 13 14	Α.	General: 1. Furnish all labor, materials, tools, equipment and services for seeding in accordance with provisions of Contract Documents. 2. Completely coordinate with work of all other trades. 3. See Division 1 for General Requirements.	10 11 12 13 14
16 17 18 19 20	В.	Related work specified elsewhere: 1. Section 02260 - Topsoiling. 2. Section 02220 - Earthwork. 3. Section 02221 - Trenching, Backfilling, and Compacting.	16 17 18 19 20
21 22	С.	Location of work: All disturbed areas, exclusive of lined landfill area.	21 22
23 24 25	1.02	QUALITY ASSURANCE	23 24 25
26 27 28 29	Α.	Fertilizer testing: Current methods of Association of Official Agricultural Chemists. 1. Testing will be conducted at discretion of Engineer.	26 27 28
30 31	1.03	SUBMITTALS	29 30 31
32 33	Α.	See Section 01300.	32
34 35 36 37 38 39	B.	Certificates for each grass seed mixture, stating botanical and common name, percentage by weight, and percentages of purity, germination, and weed seed. Certify that each container of seed delivered is fully labeled in accordance with Federal Seed Act and equals or exceeds specification requirements.	34 35 36 37 38 39
40 41 42	С.	Copies of invoices for fertilizer, showing grade furnished and total quantity applied.	40 41 42
43 44 45	PART 2	2 - PRODUCTS	43 44
45 46 47	2.01	MATERIALS	45 46 47
48 49 50	Α.	Establish a smooth, healthy, uniform, close strand of grass from specified seed.	48 49
51 52 53	В.	Grass seed: Fresh, clean, new-crop seed. 1. Species, proportions and minimum percentage of purity,	50 51 52 53

		Botanical	Pct.	Min.	Min.	(
		and Common Name	by Weight	pct. Germ	pct. Purity	(
		Kentucky 31 Fescue	100	=== = 80	97.0	(
			_			(
	С.	Mulch: Clean, seed-free, thronger, beans, or other locally a	available n	nulch mate	rial.	
	•	1. Do not use mulch containing seeds or other species the	ng a quanti at will be	ty of mat detriment	cured noxious weed cal to seeding, or	-
• •		provide a menace to surro	unding land	i.	•	
		Do not use mulch material or which is decomposed an	d will smot	ther or re	etard growth of	,
		grass.			·	
	D.	Fertilizer: Commercial ferti applicable requirements of St	lizer of 10 ate and Fed)-10-10 ar ieral law.	nalysis, meeting	
		1. Do not use cyanamic compo	unds of hy	drated lim	ne.	
	Ε.	Limestone: agricultural grad	e ground l	imestone (containing not	
		less than 85 percent of combi 1. 50 percent passing 100 me	ned calciu sh sieve.	m and magi	nesium carbonates.	
		2. 90 percent passing 20 mes	h sieve.			
	F.	Asphalt binder: Emulsified a	sphalt per	State Sp	ecifications.	
	G.	Water: Potable, free of subs	tances har	mful to g	rowth.	
	Н.	Erosion Control Matting: Pro	vide "Hold	-Grow" ty	pe erosion control	
	,	nets or approved equal. Cont matting as required on slopes	ractor sha	ll provid	e erosion control	
<u> </u>		vegetative cover.	, 4,14 4,55	,,,,,,,		
i i 2	.02	DELIVERY, STORAGE AND HANDLING	à			
<i>7</i> }	Α.	Deliver seed in standard sea	led contain	ers label	ed with producer's	
)	,,,,	name and seed analysis, and culture Rules and Regulations	in accord w	ith US De	partment of Agri-	
) [_					
2	В.	Deliver fertilizer in origina analysis.	al Containe	ers labele	d With Collect	
1 5		-				
5 P	ART	3 - EXECUTION				
	.01	JOB CONDITIONS				
9 0	Α.	Perform spring seeding betwe	en March 1	and May 1	, and fall	
1 2		seeding between September 15 the Engineer.	and Noveml	per 15, or	r upon approval of	

01	3.02	SOIL PREPARATION	01 02
02 03 04	Α.	Limit preparation to areas which will be planted soon after preparation.	03 04 05
05 06 07	В.	Loosen surface to minimum depth of four (4) IN.	06 07
08 09	С.	Remove stones over one (1) IN in any dimension, sticks, roots, rubbish and other extraneous matter.	08 09 10
10 11 12 13 14 15	D.	Test soil pH using test kits approved by USDA NRCS. Use test results to determine rate of lime application needed to make soil circumneutral. Engineer will approve application rate prior to its application.	11 12 13 14 15
16 17 18	Ε.	Spread lime uniformly over designated areas at rate determined by soil testing.	16 17 18
19 20 21 22 23	F.	After application of lime, prior to applying fertilizer, loosen areas to be seeded with double disc or other suitable device if soil has become hard or compacted. Correct any surface irregularities in order to prevent pocket or low areas which will allow water to stand.	19 20 21 22 23
24 25 26 27	. G.	Test soil fertility according to USDA NRCS approved methods. Use test results to determine rate of fertilizer application. Engineer will approve fertilizer application rate prior to application.	24 25 26 27
28 29 30	H. ⊕	Distribute fertilizer uniformly over areas to be seeded at a rate determined by soil testing. 1. Use suitable distributor.	28 29 30
31 32 33 34	## ##	 Incorporate fertilizer into soil to depth of at least two (2) IN. Remove stones or other substances which will interfere with turf development or subsequent mowing. 	31 32 33 34
35 36 37 38 39	I.	Grade seeded areas to smooth, even surface with loose, uniformly fine texture. 1. Roll and rake, remove ridges and fill depressions, as required to meet finish grades. 2. Fine grade just prior to planting.	35 36 37 38 39
40 41 42	J.	Restore seeded areas to specified condition if eroded or otherwise disturbed between fine grading and planting.	40 41 42
43 44 45 46	Κ.	If fertilizer application rate is determined (by invoices submitted) to be less than that specified, apply additional fertilizer.	43 44 45 46
47 48	3.03	SEEDING	47 48
49 50 51 52 53	Α.	Temporary Seeding: 1. Do not use seed which is wet, moldy, or otherwise damaged. 2. Seed the appropriate species for the planting season as specified in 2.01 A.4. 3. Employ satisfactory methods of sowing using mechanical power	49 50 51 52 53

driven drills or seeders, or mechanical hand seeders, or other approved equipment. 4. Evenly apply seed at the following rates: Rate (1b/acre) Species Winter Rye Small grains should be planted no more than 1 inch deep, and grasses no more than 1/2 inch deep. Lightly rake seed into soil followed by light rolling or 11. cultipacking. .12 Anchor straw by tacking with emulsified asphalt or netting or 7. other methods approved by Engineer. Inspect all seeded areas and make necessary repairs of re-seedings within planting season, if possible. If stand is over 60% damaged, re-establish planting area following recommendations specified for lime, fertilizer and seeding. Clean-up: Remove any soil or similar material from paved areas within same working day. Upon completion of seeding, remove all excess soil, stones, and other debris from site or dispose as directed by Owner. Repair all damages to existing construction caused by lawn operations to the satisfaction of Architect and Owner at no additional cost to Owner. B. Do not use seed which is wet, moldy, or otherwise damaged. Use approved mechanical power driven drills or seeders, or mechanical 27 hand seeders, or other approved equipment. Distribute seed evenly over entire area at not less than 7LB/1000 SF, 30 50 percent sown in one direction, remainder at right angles to first sowing. Stop work when work extends beyond most favorable planting season for species designated, or when satisfactory results cannot be obtained because of drought, high winds, excessive moisture, or other factors. Resume work only when favorable condition develops. Lightly rake seed into soil followed by light rolling or Culti-packing. Immediately protect seeded areas against erosion by mulching or Н. placing netting. Spread mulch in a continuous blanket using 1-1/2 TON/ACRE to depth of 4 or 5 straws. Immediately following spreading mulch, secure with evenly distributed emulsified asphalt at rate of 200 gal/acre. Protect all seeded slopes greater than 2:1 (horizontal to vertical) against erosion with approved erosion control netting or mats.

01	I.	Immediately after planting, water to a depth of 2 inches.	01
02			02
03	3.04	MAINTENANCE	03
04			04
05	Α.	Remulch with new mulch in areas where mulch has been disturbed by	05
06		wind or maintenance operations sufficiently to nullify its purpose.	06
07		Anchor as required to prevent displacement.	07
08		·	08
09	В.	Replant bare areas using same materials specified.	09
10			10
11	· C.	Contractor shall supply sufficient water until grass is established.	1.1
12			12
13			13
14		END OF SECTION	14
	5	·	



01		SECTION 02240	01
02 03 04		OPERATIONAL COVER AND LEACHATE COLLECTION LAYER	02 03 04
05 06	PART 1	1 - GENERAL	05 06
07 08 09	1.01	DESCRIPTION	07 08 09
10 11 12 13 14 15 16 17 18 19 20	Α.	 General: Furnish all labor, materials, tools, equipment and services for installation and placement of the operational cover and leachate collection layer, as indicated, in accordance with provisions of Contract Documents. Completely coordinate with work of all other trades. Although such work is not supplementary or miscellaneous items, appurtenances and devices incidental to or necessary for a sound, secure, complete and compatible installation. See Division 1 for General Requirements. 	10 11 12 13 14 15 16 17 18 19
21 22	1.02	RELATED WORK SPECIFIED ELSEWHERE	20 21 22
23 24	Α.	Section 02220: Earthwork.	23 24
2 4 25 26	В.	Section 02276: Soil Liner System.	25 25
27 28	С.	Section 02775: Geosynthetic Liner System.	27
29 30	D.	Section 02900: Geotextiles.	28 29
31	E.	Section 15064: Pipe: Plastic.	30 31
32 33 34	1.03	QUALITY STANDARDS	32 33 34
35 36 37 38 39 40 41 42 43 44 45 46	Α.	Referenced Standards 1. American Society for Testing and Materials: a. D422 - Particle Size Analysis. b. D2434 - Permeability of Granular Soils. c. D4373 - Calcium Carbonate Content of Soils. d. D5084 - Measurement of Hydraulic Conductivity of Saturated Porous Materials Using a Flexible Wall Permeameter. 2. North Carolina Department of Transportation (NCDOT), Standard Specifications for Roads and Structures, 1990 or current edition. 3. Refer to "Construction Quality Assurance Plan" prepared for Hanes Mill Landfill Lateral Expansion.	35 36 37 38 39 40 41 42 43 44 45
47 48	1.04	SUBMITTALS	47 48
49 50 51	Α.	See Section 01300: Submittals.	49 50
52 53	В.	At least four weeks prior to construction of the leachate collection layer, submit a bulk sample of each material from each	51 52 53

The Contractor shall exercise care in maintaining a true line and

1,1

- D. Materials shall be placed over the Geomembrane only after areas have been released by the Geomembrane Installer and the CQA Consultant. The materials shall be placed as specified below.
 - 1. All materials shall be placed and spread with low ground pressure equipment (6 psi ground pressure or less) as approved by the Engineer to reduce potential damage to the Geomembrane. The Geomembrane surface shall be off limits to construction traffic. Excessive hard turning of tracked equipment on the stone must be avoided.
 - 2. At least 12 IN (12") of separation between the Geomembrane and equipment shall be maintained.
 - Material shall not be placed over standing water or ice.
 - 4. Material shall not be compacted within the cell limits.

- E. The leachate collection layer shall be spread in a manner that minimizes development of folds in the Geomembrane. Any portions of the Geomembrane that develop crimp shall be repaired by the Geomembrane Installer at no expense to the Owner.
 - 1. If during spreading, excessive wrinkles develop, the Contractor shall adjust placement and spreading methods, or cease until the Geomembrane cools and wrinkles decrease in size.
 - 2. Wrinkles that exceed approximately 6 inches in height and cannot be eliminated by amended placement and spreading methods shall be cut and repaired by the Geomembrane Installer in a method approved by the CQA Consultant.

F. Any damage to the underlying Soil or Geomembrane Liners or Geotextiles or shall be repaired in accordance with the applicable section of these Specifications at Contractor expense.

3.5

G. Stockpiling of materials within the limits of the cell shall be subject to advanced approval by the CQA Consultant. Any hauling equipment (dump trucks, etc.) operating within the cell limits, including access ramps, shall have a minimum of 3-ft. of separation between the vehicle wheels and the Geomembrane.

H. Any areas where unauthorized or tracked equipment has operated over the leachate collection system shall be subject to investigation for potential Geomembrane damage. Such investigations may include removal of overlying materials in the affected areas and visual inspection of the Geomembrane. These activities shall be conducted under direction by the CQA Consultant at Contractor's expense.

I. Test areas to evaluate potential damage due to equipment operations may be required by the CQA Consultant to assess equipment to be used by the Contractor. The test area shall be outside the cell limits, use scrap materials not to be used in cell construction, and model construction conditions as closely as is practical. Test area parameters shall be determined by the CQA Consultant and Contractor in advance of construction of the leachate collection

01	system.								
02 03 04 05	3.02 QUALITY C	CONTROL			02 03 04				
	A. The CQC Consultant shall perform testing of the materials.								
06 07	B. Ensure CQA Consultant has at all times immediate access for the								
80	testing	of all related work.	,, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		08 09				
09 10		TABLI	E A .		10 11				
11 12 13		Minimum CQC Tes	ting Frequency		. 12				
14 15		•			14 15				
16			Minimum Sample Frequency/	Acceptance	16 17				
17 18 19 20 21 22 23 24 25	Components	Required Test	Location	Criteria	18 19				
	Leachate Collection	1. Permeability (ADTM D2434)	1 per 2000 CY	$K \ge 1 \times 10^{-1} \text{ cm/sec}$	20 21 22				
	Stone Layer	2. Carbonate Content (ASTM D4373)	l per source	<15% by weight	23 24 25 26				
26 27		3. Thickness	l per acre	12" to 14"	27				
28 29 30 31 32 33 34 35 36 37	Leachate Collection	1. Gradation (ADTM D422)	1 per 1500 CY	NCDOT No. 57 Stone	28 (29 30				
	Stone Around Piping	Carbonate Content (ASTM D4373)	1 per source	<15% by weight	31 32 33 34				
	Operational Cover Soil	1. Permeability (ASTM D2434 or ASTM D5084)	1 per 2000 CY	$K \ge 2 \times 10^{-5} \text{ cm/sec}$	35 36 37				
38 39 40 41	•	2. Thickness	l per acre	12" to 14"	38 39 40 41				
41	END OF SECTION								

```
SECTION 02276
                                                                                       01
01
                                                                                       02
02
                                                                                       03
                                  SOIL LINER SYSTEM
03
                                                                                       04
04
                                                                                       05
05
                                                                                       06
06
    PART 1 - GENERAL
                                                                                       07
07
                                                                                       08
    1.01 SUMMARY
08
                                                                                       09
09
10
           Section Includes:
                                                                                       10
           1. Contractor to furnish all labor, materials, tools, equipment,
                                                                                       11
11
            and services for soil liner components as indicated, in accordance
                                                                                       12.
12
            with provisions of Contract Documents.
                                                                                       13
13.
                                                                                       14
            2. Completely coordinate with work of all other trades.
14
                                                                                       15
                Although such work is not specifically indicated, furnish and
15
                install all supplementary or miscellaneous items, appurtenances
                                                                                       16
16
                                                                                       17
17
                and devices incidental to or necessary for a sound, secure and
                                                                                       18
                complete installation.
18
                                                                                       19
19
                                                                                       20
          Related Sections include but are not necessarily limited to:
20
                Section 02110 - Site Clearing.
                                                                                       21
21
                                                                                       22
                Section 02200 - Earthwork.
            2.
22
                                                                                       23
                Section 02775 - Geosynthetic Liner System.
23
                                                                                       24
                Construction Quality Assurance Plan.
24
                                                                                       25
25
                                                                                       26
    1.02 QUALITY STANDARDS
26
                                                                                       27
27
            Reference Standards:
                                                                                       28
28
                                                                                       29
29

    ASTM - American Society for Testing and Materials

                                                                                       30
30
                   ASTM D-422 - Particle Size Analysis
                                                                                       31
                b. ASTM D-698 - Standard Proctor
31
                c. ASTM D-854 - Specific Gravity
                                                                                       32
32
     70
                                                                                       33
                    ASTM D-1140- Fines Content in Soils
33
                                                                                       34
                    ASTM D-1556 - In-situ Density Measurement Using the Sand
34
                                                                                       35
35
                    Cone
                f.
                    ASTM D-1557 - Modified Proctor
                                                                                       36
36
                    ASTM D-2166 - Unconfined Compressive Strength
                                                                                       37
37
                   ASTM D-2216 - Moisture Content Using Over-Dry Method
                                                                                       38
38
                h.
                    ASTM D-2487 - Soils Classification
                                                                                       39
39
                i.
                j. ASTM D-2573 - Field Vane Shear Test
                                                                                       40
40
                    ASTM D-2922 - In-situ Density Using Nuclear Methods
41
                                                                                       41
                    ASTM D-3017 - In-situ Moisture Content Using Nuclear
                                                                                       42
42
                    Methods
                                                                                       43
43
                    ASTM D-4318 - Atterberg Limits
                                                                                       44
44
                                                                                       45
                     ASTM D-5084 - Flexible Wall permeameter
45
                USEPA - United States Environmental Protection Agency
                                                                                       46
46
                    EPA/600/R-93/182 -"Quality Assurance and Quality Control
                                                                                       47
47
                for Waste Containment Facilities," September, 1993.
Construction Quality Assurance Plan," prepared for Hanes Mill
                                                                                       48
48
                                                                                       49
49
                                                                                       50
                Landfill Expansion, dated September 1995.
50
                                                                                       51
51
           SUBMITTALS
                                                                                       52
52
     1.03
                                                                                       53
53
```

01	A. See Section 01300 - Submittals.	01 02 _/
02 03	B. Refer to the CQA Plan.	03 ¹ 04
04 05	1.04 JOB CONDITIONS	05 06
06 07	A. Verify conditions of subgrade prior to commencing work.	07 08
08 09	1.05 TOLERANCES	09 10
10 11 12 13 14 15 16	 A. The soil liner system must exceed the following tolerances: 1. The saturated hydraulic permeability of the soil liner must be equal to or less than 1.0 x 10-7 cm/sec, as determined by ASTM D5084. 2. The thickness of the soil liner must be equal to or greater than 24 inches. An overbuild of 2-inches is allowed for the 	11 12 13 14 15 16
17	soil liner.	17 18
18 19	PART 2 - PRODUCTS	19
20 21	2.01 MATERIALS	20 21 22
22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 40 41	permeability soil and certify that it is not contaminated with hazardous materials or hazardous wastes.	23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 40 41
42 43 44 45 46	B. Natural Fine-Grained Soil Classification: Natural fine-grained soil shall have a classification of CH, CL, MH, or ML as determined by ASTM D2488. 	43 44 45 46 47
47	Grain sizes shall be within the following gradation:	T/

01			Sieve Size Percent Passing by Weight	01
02				02
03 04 05			No. 4 > 90	03 04 05
06 07			No. 200 > 30	06 07
089 011 123 145 67 89 0	C.	3. 4. 5.	least 25 as measured by ASTM D4318. The plasticity index shall be at least 10 and less than 30 as measured by ASTM D4318. Compaction Equipment: a. The compaction equipment shall be suitable type and adequate to obtain densities specified, and shall provide satisfactory breakdown of materials to form a low permeability fill free of lift interface voids. The CQC Consultant shall confirm compaction equipment adequacy, and recommend changes if required, based on the soil liner test strip. Such additional equipment will be provided by Contractor at no additional cost. b. The compaction equipment shall be maintained and operated in a condition that will deliver manufacturer's rated compactive effort. c. Hand-operated equipment shall be capable of achieving specified soil densities. d. Natural fine-grained materials shall be compacted using equipment that provides a kneading action, such as a wobble-wheeled roller or a sheepsfoot roller having tines as long as the maximum lose lift thickness to ensure proper lift interface compaction. e. If a sheepsfoot is used, the finished surface of the final lift shall be rolled with a smooth steel drum roller or rubber-tired roller to eliminate tine or roller marks and provide a smooth, dense surface for geomembrane placement. Moisture Control Equipment: Equipment for applying water shall be of a type and quality adequate for the work, shall not leak, and shall be equipped with a distributor bar or other approved device to assure uniform application. Equipment for mixing and drying out material shall consist of blades, discs, or other equipment defined by the CQC Consultant as approved by the CQA Consultant. Mixing of natural fine-grained soils may also be required to get even distribution of moisture. Soil liner material must not be compacted within 24 hours of the adjustment of water content by the addition of water.	08 9 0 1 1 2 3 1 4 5 6 7 8 9 9 0 1 1 2 3 1 4 5 6 7 8 9 9 0 1 1 2 3 2 2 2 2 2 2 2 2 3 3 3 3 3 3 3 3
53		1.	Hydraulic conductivity of constructed bentonite amended soil	53

```
01
                   project or amended soil.
01
                                                                                    02
               Compaction Equipment:
02
                                                                                    03
                   Compaction equipment shall be a suitable type and adequate
03
                   to obtain soil densities specified by the CQC Consultant
                                                                                    04
04
                                                                                    05
05
                   based on the soil liner test strip.
                                                                                    06
                   Contractor shall maintain and operate equipment in such
06
                    condition that it will deliver manufacturer's rated
                                                                                    07
07
                                                                                    08
08
                    compactive effort.
                                                                                    09
                   Hand-operated equipment shall be capable of achieving
09
                                                                                    10
10
                    specified densities.
                                                                                    11
11
                   Contractor shall compact bentonite amended soil using a
                                                                                    12
                    pneumatic, tire roller or a sheepsfoot compactor.
12
                                                                                    13
           7. Moisture Control Equipment: Equipment for applying water shall
13
                                                                                    14
               not leak, and shall be equipped with a distributor bar or
14
                                                                                    15
                other device to assure uniform application as approved by the
15
                                                                                    16
16
               CQC Consultant.
                                                                                    17
17
                                                                                    18
          SOIL LINER MATERIAL ACCEPTANCE -
18
    2.02
                                                                                    19
19
           General: All imported, on-site, and processed materials specified
                                                                                    20
20
                                                                                    21
21
            in this section are subject to the following requirements:
               All tests necessary for the Contractor to locate and define
                                                                                    22
22
                acceptable sources of materials shall be made by the CQC
                                                                                    23
23
                                                                                    24
                Consultant. Certification that the material conforms to the
24
                                                                                    25
                Specification requirements along with copies of the test
25
                results from a qualified commercial testing laboratory shall
                                                                                    26
26
                be submitted to the CQA Consultant for approval at least 10
                                                                                    27
27
                days before the material is required for use. All material
                                                                                    28
28
                                                                                    29
29
                samples shall be furnished by the Contractor at the
                                                                                    30
30
                Contractor's sole expense.
                                                                                    31
31
                All samples required in this section shall be representative
32
                and be clearly marked to show the source of the material and
                                                                                    32
                                                                                    33
                the intended use on the project. Sampling of the material
33
                                                                                    34
                source shall be done by the CQC Consultant in accordance with
34
                                                                                    35
35
                ASTM D75.
                Notify the CQA Consultant at lease 24-hours prior to sampling.
                                                                                    36
36
                The CQA Consultant may, at the CQA Consultant's option,
                                                                                    37
37
                                                                                    38
                observe the sampling procedures.
38
                                                                                    39
                Tentative acceptance of the material source shall be based on
39
                                                                                    40
                an inspection of the source by the CQA Consultant and the
40
                certified test results of the Borrow Source Characterization
                                                                                     41
41
                Study (BSCS) as submitted by the Contractor to the CQA
                                                                                     42
42
                                                                                    43
43
                Consultant. No imported materials shall be delivered to the
                                                                                     44
44
                site until the proposed source and materials tests have been
                                                                                     45
45
                accepted in writing by the CQA Consultant.
46
                Final acceptance of any material will be based on results of
                                                                                     46
                tests made on material samples taken from the completed soil
                                                                                     47
47
                liner test strip, combined with the results of the BSCS. If
                                                                                     48
48
                                                                                     49
49
                tests conducted by the CQC Consultant or the CQA Consultant
                                                                                     50
                indicate that the material does not meet Specification
50
                                                                                     51
51
                requirements, material placement will be terminated until
                                                                                     52
52
                corrective measures are taken. Material which does not conform
                                                                                     53
53
                to the Specification requirements and is placed in the work
```

01 02 03 04		6.	shall be removed and replaced at the Contrac Contractor shall be solely responsible for o permits required to obtain acceptable source use in the work.	btaining all	01 02 03 04 05
05 06 07	В.		oling and testing required herein shall be do tractor's sole expense.	one at the	06 07 08
09 01 11 11 11 11 11 11 11 11 11 11 11 11	C.	 2. 3. 	Permeability Borrow Source Characterization The Contractor will be responsible for all p screening of the soil liner material at his the requirements of the specifications. The be responsible for the erosion protection of during his operation. The Contractor shall aspects of this operation with the CQC Consu Consultant, and Project Manager. CQC Consultant shall complete a BSCS of nate soils or of soil that will be used in bentor Contractor shall conduct tests, including pa Atterberg limits, moisture-density, and hydr tests, as necessary to locate an acceptable Once a potential source of material has beer Consultant shall develop and undertake a tes demonstrate the acceptability of the propose Certified results of all tests shall be sub Consultant upon completion of tests. Tentat the borrow source by the CQA Consultant will results of the study. The testing program of following elements, at a minimum: a. An excavation plan for the borrow source proposed surface mining limits and and be taken for testing. b. Test pits for borrow source sampling sh appropriately spaced to reflect site ge sampled at depth intervals appropriate excavation methods. c. A minimum of 12 samples shall be collect the parameters required as described in paragraphs. Test Parameters and Reporting for Natural F All samples collected from the proposed bor natural fine-grained soils shall be tested parameters:	own cost to meet contractor will f the stockpile coordinate all ultant, CQA ural fine-grained nite amended soils. article size, raulic conductivity source of material. n located, the CQC sting program to ed material. mitted to the CQA tive acceptance of l be based upon the shall include the e indicating depths of samples to all be omorphology and to the proposed ted and tested for the following ine-grained Soils: row area for	09 10 11 12 13 14 15 16 17 18 19 20 21 22 22 24 25 26 27 28 29 30 31 32 33 33 34 35 36 36 36 37 37 38 37 38 37 37 37 37 37 37 37 37 37 37 37 37 37
44 45 46			Parameter	Test Method	44 45 46
47 48			Particle Size (sieve plus hydrometer)	ASTM D422	47 48 49
49 50 51			Atterberg Limits	ASTM D4318	50 51
52 53			Moisture-Density	ASTM D698	52 53

01				Hydra	aulic Conductivi	ity(1)		ASTM D5084		01 02	
02 03 04 05 06				(1)	Hydraulic condurecompacted sam compacted accordant usin accordance with	nples of the rding to cri ng data from	e proposed teria dev n tests co	material, eloped by th		03 04 05 06 07	
08 09 10 11			6.	a. Para	ameter for Soil meters and repon ded soil shall b	rting for so	oils to be	used in ber	ntonite	08 09 10 11 12	
12 13 14 15				b. Tests required under this paragraph are part of the BSCS. Additional tests on the bentonite amended soil product are required for soil liner acceptance. See 2.01E.						13 14 15 16	
16 17 18 19 20 21		D.	Natı 1.	Followin soils, t Consulta	ral Fine-Grained Soils Conformance Testing: Following acceptance of a source for natural fine-grained Foils, the following tests shall be performed by the CQC Fonsultant on samples taken from the excavated soil liner Formaterial using the methods and at the frequencies indicated Foelow:						
23 24	.:			Te	st	Test Method	i	Minimum Free	quency	23 24	
25 26	ej Nj			==	==	========	=	==== ======	=====	25 26	
27	z - *			Pe	rcent Fines	ASTM D422		1 per 5,000	cu yd	27 28	
28 29				At	terberg Limits	ASTM D4318		1 per 5,000	cu yd	29 30	
30 31 32	A.			Мо	isture-Density	ASTM D698		1 per 10,000	O cu yd	31 32	
33 34	•		2.	in test	Consultant shal results is occu					33 34	
35 36 37			3.	The CQA	cifications. Consultant may the accuracy of					35 36 37	
38 39			4.	Consulta If tests	nt. indicate mater	ial does no	t meet Spe	cification		38 39	
40 41					ents, Contracto rrective measur			cerial place	ment	40 41	
42			5.	Contract	or shall remove	and replac	e materia]			42	
43 44				meet Spe Owner.	cification requ	irements at	no additi	ional cost t	o the	43 44	
45 46		Ε.	Ben		ended Soil Conf					45 46	
47 48			1.		g acceptance of e amended soils					47 48	
49				Design M	lix Analysis and	submit cer	tification			49	
50 51			2.		e material as d Hix Analysis:	escribed be	low.			50 51	
52 53				a. Coll	ect two of the approved borrow					52 53	

be solely at the Contractors expense.

2. Drying, blending, or wetting required to maintain the soil liner soil at a suitable moisture content shall be solely at the Contractors expense.

PART 3 - EXECUTION

3.01 INSTALLATION

A. The subgrade to be lined shall be smooth and free of vegetation, sticks, roots, and debris. It shall be the responsibility of the Contractor to keep the receiving surfaces in the accepted condition until complete installation of the liner is accomplished.

11.

B. The subgrade shall be proofrolled with a pneumatic tired vehicle of at least 20 tons GVW, making passes across the area as directed by the CQC and/or CQA Consultants. The soil liner shall not be placed over areas deemed unacceptable by either the CQC or CQA Consultants based on proofroll observations or inadequate test results.

C. The soil liner shall be installed in four compacted lifts of approximate equal thickness.

D. When particles exceeding 3/4" are observed at the final lift surface, they shall be removed by hand prior to final rolling of the surface.

E. Equipment shall be used such that bonding of the two lifts will occur. Equipment shall have cleats or other protrusions of such length necessary to completely penetrate into the loose lift. Compaction shall be performed using appropriately heavy, properly ballasted, penetrating foot compactor making a minimum number of passes as approved by the CQC Consultant and CQA Consultant based on the soil liner test strip.

42.

F. If desiccation and crusting of the lift surface occurs prior to placement of the next lift, this area shall be scarified to a minimum depth of two inches or until sufficiently moist materials are encountered, whichever is greater. After scarification, the superficial material should be reworked to obtain a moisture content at least two percent above optimum moisture content. Alternately, the drier superficial soil may be stripped and mixed with additional moist soil to achieve a moisture content satisfying the project requirements.

G. No frozen material shall be placed.

H. Material shall not be placed on a previous lift which is frozen. Frozen in-place material shall be removed prior to placement of additional soil material.

 Material which has been subjected to a freeze/thaw cycle(s) shall be disked and recompacted prior to placement of subsequent lifts. 12.

- J. During construction, exposed finished lifts of the soil liner material should be sprinkled with water to minimize desiccation, as necessary. The Contractor is responsible to protect the soil liner from rain, drying, desiccation, erosion and freezing. All defective areas shall be repaired by the Contractor to the satisfaction of the CQC Consultant at no extra compensation.
- K. At the end of each day's construction activities, completed lifts or sections of the compacted soil liner should be sealed. Common sealing methods include rolling with a rubber tired or smooth-drum roller, backdragging with a bulldozer, or placement of temporary cover soil over the compacted soil liner. The compacted soil liner should be sprinkled with water, as needed.
- L. If testing shows that a lift is significantly thicker than six inches, the top of the lift will be shaved off so that the lift is approximately six inches thick.

3.02 SOIL LINER TEST STRIP

- A. Test Strip Installation:
 - 1. Prior to actual soil liner installation, a soil liner test strip of a dimension no less than 100 feet long by 30 feet wide by 2 feet thick shall be constructed by the Contractor over a compacted subgrade within the liner construction site.
 - 2. The soil liner test strip shall be constructed using the same equipment and construction procedures that are anticipated for use during actual liner installation.
 - 3. During test strip installation, the Contractor in coordination with his CQC Consultant and the CQA Consultant shall determine the field procedures that are best suited for his construction equipment to achieve the requirements specified herein.
 - 4. If the test strip fails to achieve the desired results, the soil material of the strip shall be completely removed, and additional test strip(s) shall be constructed until the requirements are met.
 - 5. The CQC Consultant shall document that the subgrade of the test strip liner is properly compacted to at least 95 percent of the maximum dry density, as determined using the Standard Proctor test (ASTM D-698). Field density tests on the subgrade shall be performed by the CQC Consultant and documented at a minimum of three test locations within the test strip area:
 - 6. At least five field density measurements shall be performed by the CQC Consultant on each lift of the liner test strip. The field density tests shall be conducted using a nuclear gauge (ASTM D-2922) or other method, as approved by the CQA Consultant. Corresponding tests for moisture content to determine dry density shall likewise be performed by using a nuclear gauge (ASTM D-3017), or other approved method. On the

test pad, the density measurement if performed by a nuclear gauge shall be verified through performance of one sand cone tests (ASTM D-1556) or drive tube test (ASTM D-2937) at a location selected by the CQA Consultant. The moisture content measurement, if performed by a nuclear gauge shall be verified by recovering at least five samples for oven-dry testing (ASTM D-2216) from the test location.

7. Upon completion of the soil liner test strip, the CQC Consultant, as observed by the CQA Consultant, shall measure the thickness of the test strip at a minimum of five random locations.

8. A minimum of five random samples of the liner construction materials delivered to the site during test strip installation shall be tested by the CQC Consultant for moisture content (ASTM D-2216), sieve analyses (ASTM D-421, D-422) and Atterberg limits (ASTM D-4318).

 The CQC Consultant shall conduct at least one standard Proctor (ASTM D-698) and one modified Proctor (ASTM D-1557) compaction test on bag samples of the test strip material to determine the moisture-density relationships.

A minimum of five undisturbed samples shall be taken from the test strip by the CQC Consultant for laboratory hydraulic conductivity testing. The samples shall be taken within a two-foot radius of the in-situ density and moisture tests. The CQA Consultant may also conduct independent hydraulic conductivity testing. Laboratory hydraulic conductivity testing shall be conducted using constant head, triaxial type permeameters (ASTM D-5084). The test specimens shall be consolidated under an isotropic effective consolidation stress determined by the CQA Consultant and permeated with water under a back pressure of at least 10 pounds per square inch (psi) to achieve saturation. The inflow to and outflow from the specimens shall be monitored with time and the coefficient of permeability calculated for each recorded flow increment. test shall continue until steady state flow is achieved and relatively constant values of coefficient of permeability are

11. Optional: The data gathered from the test strip sampling (i.e., field density, moisture, undisturbed samples, and in-situ hydraulic conductivity) shall be used along with the Proctor curve for the soil to develop a range of acceptable moisture and density test values which are likely to result in a maximum permeability no greater than 1 x 10-7 cm/sec. This range of moisture/density values will be established by the CQC Consultant and the CQA Consultant and will be utilized as a means to establish Pass/Fail Criteria for the remainder of the area to be lined by the subject material.

area to be lined by the subject material.

12. The test strip will be considered acceptable if the measured hydraulic conductivity of the test strip as determined by ASTM D-5084 meets the requirements of the specifications.

13. If field and laboratory test data indicate that the installed test strip meets the requirements of this Specification, it may be used as part of the liner provided that it is adequately

protected by the Installer from drying and equipment damage after installation. The Installer shall scarify the liner material along the edge of the test strip. A minimum 2-foot overlap per lift is required for mixing and compaction between the test strip and the liner. Upon receipt of the test data from the CQA Consultant, the Project Manager shall inform the Contractor if the test strip can remain in-place as part of the liner. FIELD QUALITY CONTROL AND QUALITY ASSURANCE 3.03 11. Refer to the CQA Plan. Α. The following field and laboratory quality control tests shall be performed by the CQC Consultant at no additional expense to the Owner during soil liner construction: Density/Moisture: Conduct at least one field density test per 100' x 100' grid area per lift of compacted liner. Field .18 density tests shall be conducted using a nuclear gauge (ASTM D-2922), or other method as approved by the CQA Consultant. Corresponding tests for moisture content to determine dry density shall likewise be performed using a nuclear gauge (ASTM D-3017), or other approved method. As a check of the nuclear methods, perform one drive tube density (ASTM D-2937) determination once for every fifty nuclear tests and a series of five oven-dry (ASTM D-2216) samples after each set of 25 nuclear moisture content tests. Thickness: Using a 1 IN auger and/or probe at a frequency no less than four tests per acre per lift of installed soil liner measure the thickness of the soil liner. Thickness measurements shall be observed by the CQA Consultant. Atterberg Limits: Perform Atterberg Limits on at least one sample per acre per lift of installed liner. This may be waived by the CQA Consultant if permeability requirements are Fines Content: Determined at a minimum frequency of one test (ASTM D-1140) per acre per lift of installed liner. Hydraulic Conductivity (ASTM D-5084): Test at a minimum frequency of one test per acre per lift. Laboratory Compaction Tests: Re-evaluated after each increment of 5,000 cubic yards is placed. If there are indications of a change (e.g., visual appearance) in product quality between shipments, additional tests shall be performed as necessary. Holes in the compacted soil liner created as a result of destructive testing (i.e., thin-walled shelby tube sampling, field density determinations and thickness measurements) shall be backfilled and tamped by rod uniformly in 2 inch thick lifts. The backfill material shall be the same liner construction material or hydrated bentonite powder, if approved

by the CQA Consultant. On the surface, the backfill material

shall extend slightly beyond the holes to make sure that a good

tie in with the surrounding liner is achieved. Repaired areas

:

1.2

shall be observed and documented by the CQC Consultant.

- B. Give minimum of 24 HR advance notice to CQA Consultant when ready for soil testing and inspection in completed area of the soil liner.
- C. For areas not meeting field and laboratory testing criteria, the Contractor shall scarify the full depth of the lift or replace the material as needed. The material shall be reshaped, rewetted as needed, rehomogenized and recompacted to the specified density. Areas not meeting the thickness requirements shall be augmented with additional materials. The added materials shall be reworked with the soil layer to ensure homogeneity and proper bonding. This may be done by scarification of the surface prior to addition of new material. The repaired area shall be properly documented, and field and laboratory quality control testing shall be performed to ensure the repaired liner section meets the requirements specified herein.
- D. The Contractor shall pay for all costs associated with corrective work and retesting resulting from failing compaction density tests.
- E. The soil liner materials on the landfill base shall be compacted to no less than 95 percent of the Standard Proctor (ASTM D-698) dry density corresponding to the molding moisture content.

END OF SECTION

.

01		SECTION 02515	01
02 03 04		HDPE MANHOLE STRUCTURES	02 03 04
05 06	PART :	. – GENERAL	05 06
07 08 09 10 11 13 14 15 16 17 18 19 20 21 22 22 24 25 26 27 28 29	1.01	DESCRIPTION	07 08
	Α.	 General: Furnish all labor, materials, tools, equipment and services for all manhole structures with appurtenant items and pipe in accordance with provisions of the Contract Documents. Completely coordinate with work of all other trades. Although such work is not specifically indicated, furnish and install all supplementary or miscellaneous items, appurtenances and devices incidental to or necessary for a sound, secure and complete installation. 	09 10 11 12 13 14 15 16 17 18
	В.	Work included consists of, but is not necessarily limited to: 1. Leachate management devices and manholes.	20 21
	С.	Related Sections include, but are not necessarily limited to: 1. Section 02221 - Trenching, Backfilling and Compacting 2. Section 02775 - Geosynthetic Liner System. 3. Section 03002 - Concrete. 4. Section 15060 - Pipe and Pipe Fittings: General. 5. Section 15064 - Pipe: Plastic. 6. CQA Plan.	22 23 24 25 26 27 28 29
30 31 32	1.02	QUALITY STANDARDS	30 31 32
33 34	Α.	Referenced Standards:	33 34
35 36 37		ASTM D- 883 Definition of Term Relating to Plastics ASTM D-1248 Specification for Polyethylene Plastics	35 36
38 39		Molding and Extrusions Materials ASTM D-2122 Determining Dimensions of Thermoplastic Pipe and Fittings.	37 38 39
40 41	1.03	SUBMITTALS	40 41
42 43	Α.	See Section 01300.	42 43
44 45 46 47	В.	Include detailed diagrams for manholes showing components and dimensions.	44 45 46
48 49	С.	Indicate elevation and position of all piping and appurtenances of each manhole.	47 48 49
50 51 52 53	D.	Provide fabrication drawings indicating proposed welding procedures, bracing, and other pertinent information regarding manhole	50 51 52

```
01
01
           Production Dates: Submit statement of production dates for the
                                                                                    02
02
                                                                                    03
           resin and the geosynthetic for this work.
03
                                                                                    04
04
           Factory Test Results and Material Certification: Submit factory
                                                                                    05
05
           test results of materials demonstrating conformance with the
                                                                                    06
იგ
           requirements of these Specifications. In addition, submit the
                                                                                    07
07
           Manufacturer's certification that the material delivered is similar
                                                                                    08
80
           and the same formulation as that for which test results are
                                                                                    09
09
           submitted. Submittal shall be prior to or concurrent with product
                                                                                    10
10
                                                                                    1.1
           delivery.
11
                                                                                    12
12
           Butt-fused welds created at the factory shall be ultra-sonically
                                                                                    13
13
           tested or by some other appropriate means, as approved by the
                                                                                    14
14
           Project Manager. A written certification of the test results shall
                                                                                    15
15
           be submitted by the manufacturer, prior to delivery to the job site.
                                                                                    16
16
                                                                                    17
17
                                                                                    18
18
                                                                                    19
    PART 2 - PRODUCTS
19
                                                                                    20
20
                                                                                     21
            ACCEPTABLE MANUFACTURERS
    2.01
21
                                                                                     22
22
            Subject to compliance with the Contract Documents, the following
                                                                                     23
23
                                                                                     24
            Manufacturers are acceptable:
24
                                                                                     25
                Manholes:
25
                                                                                     26
                   Advanced Drainage Systems, Inc. (ADS)
                a.
26
                                                                                     27
                    Driscopipe 1000
 27
                b.
                                                                                     28
                    Spirolite by Chevron
 28
                                                                                     29
                    Approved equal
 29
                d.
                                                                                     30
                Pipe (If used for manhole construction)
30
                                                                                     31
                    Driscopipe 1000
 31
                                                                                     32
                    Polypipe PE 3408
 32
                b.
                                                                                     33
                    Plexco by Chevron
                С.
 33
                                                                                     34
                    Approved equal
 34
                d.
                                                                                     35
 35
                                                                                     36
     2.02 MANHOLES AND APPURTENANCES AND PIPE
 36
                                                                                     37
 37
                                                                                     38
 38
            Materials:
        Α.
                                                                                     39
                Manholes: Polyethylene Manholes shall be produced using
 39
                                                                                     40
                polyethylene compounds conforming to the requirements of Type
 40
                III, Category 5, Grade P34, Class C, as defined and described
                                                                                     41
 41
                                                                                     42
                in ASTM D-1248. Clean reworked material or reprocessed
 42
                material may be used in the manufacture provided that the
                                                                                     43
 43
                manhole components meet all of the requirements of this product
                                                                                     44
 44
                specification. Manholes may be constructed of factory seamed
                                                                                     45
 45
                 pipe if the size and SDR are available. In that case, pipe
                                                                                     46
 46
                 criteria in these specifications applies.
                                                                                     47
 47
                 Pipe: High Density Polyethylene Pipe, solid wall shall conform
                                                                                     48
 48
                                                                                     49
                 to requirements of ASTM D-1248 Classification Type III, Class C,
 49
                 Category 5, Grade P34; ASTM D-3350 Classification PE345434C.
                                                                                     50
 50
                                                                                     51
                 The pipe shall conform to SDR rating as depicted on the
 51
                                                                                     52
 52
                 drawings.
```

01	В.	Manı	ıfacture:	01
02		1.	Manholes shall be produced in the rotational molding process.	02
03			The manhole will consist of an appropriate combination of base,	03
04			elevation, and top section based on project requirements.	04
05		2.	Manholes shall be completely constructed, including all outlets,	05
06		٠. •	and appurtenances at the facility which manufactures the	06
				07
07			manhole. Field fabrication of any manhole components by the	
80		_	Contractor is not acceptable.	08
09		3.	Manholes shall be designed so that a portable ladder can be	09
10		•	supported by the installed manhole.	10
11		4.	The bottoms of the manholes shall be 2" thick and butt-fused to	ļ1
12			the manhole body.	12
13	•	5		13
14			to the larger portion of the manhole.	14
15			or one ranger per even or one mannerer	15
16	С.	Dog	uirements:	16
17	٠.			17
		1.	Workmanship: Exterior and interior surfaces shall be	
18			relatively smooth with no sharp projections. The surfaces	18
19			shall be free of foreign inclusions and major surface defects.	19
20			Polyethylene pipe shall be as uniform as commercially practical	20
21			in color, opacity, density, and other physical properties. The	21
22			product function shall be considered when judging external	22
23			defects.	23
24		2.	Dimensions: As depicted on the drawings.	24
25		3.	Wall Thickness: Wall thickness of all components shall be	25
26			determined in accordance with ASTM D-2122 and shall have a	26
27			minimum standard dimension ratio of 32.5, or as shown on the	27
28			plans.	28
29		4.	Fabrication: Inlet and outlet openings and connecting devices	29
	* .	٠.	may be februared utilizing extrusion welding techniques	
30			may be fabricated utilizing extrusion welding techniques.	30
31			Fittings, gaskets, and accessories shall be chemically	31
32			compatible with leachate and be as recommended by the	32
33			manufacturers of the manhole segments.	33
34		5.	Compressive Strength: Manholes shall have compressive strength	34
35			which shall be determined in accordance with ASTM D-2412	35
36			modified pipe stiffness test. Pipe stiffness values shall be	36
37			12 psi min. at 5% deflection, including joints. Axial	37
38			compressive strength shall exceed 10,000 pounds at deflection	38
39			less than 3%.	39
40			1035 Bildit Old.	40
41	2.03	CULI	RCE QUALITY CONTROL	
	2.03	300	RCE QUALITY CONTROL	41
42		т	t	42
43	Α.		ts and Inspections	43
44		1.		44
45		2.	Each manhole shall be factory tested and certified water tight.	45
46		3.	Each manhole, upon delivery to the site, shall be accompanied	46
47			with factory test certification.	47
/ Q				40

01 02	PART 3	- EXECUTION	01 02 03
03	3.01 i	EXAMINATION	04 05
	Α.	Contractor shall examine and verify conditions affecting installation of the manholes prior to commencing work.	06 07 08
	3.02	INSTALLATION/ERECTION	09 10
	Α.	Manholes 1. Install in 12" leveling bed of crushed rock or gravel. 2. Concrete shall be placed around the manhole in the annular space between the outside surface and the excavation to the dimensions shown on drawings.	11 12 13 14 15
16 17		 Install plumb and to grade for entering and exiting piping. Exercise care to protect in entering and exiting piping. 	16 17
18 19 20 21 22 23 24 25 26 27 28 29	В.	Pipe 1. Install as indicated on the drawings. 2. Install to line and grade as indicated. 3. Only the butt fusion welding of solid pipe is acceptable. 4. Pipe penetrations through the liner shall only be made by using prefabricated pipe boots.	18 19 20 21 22 23 24
	3.03	QUALITY ASSURANCE AND QUALITY CONTROL	26
	Α.	The CQA Consultant shall inspect manholes prior to installation for physical damage and report to the Project Manager.	28 29 30
30 31 32	В.	The Contractor shall develop and submit schedule for testing of manholes and appurtenant piping.	3: 3: 3:
33 34	С.	Tests shall be witnessed by the CQA Consultant.	3. 3.
35 36 37 38 39 40 41 42 43 44 45 46		The Contractor shall hydrostatically test each manhole and header pipe section by filling with water and securing the opening to prevent evaporation. Duration of test shall be 48 hours.	3 3 3 3
	Ε.	Manholes and piping will be accepted if no water is lost during the 48 hour test period, at the discretion of the Project Manager or CQA Consultant.	4 4 4 4
	F.	Manholes and piping which leak shall be repaired by the Contractor at no additional cost to the Owner.	4 4 4 4
47 48		END OF SECTION	4

01		SECTION 02775 0	
02 03 04		HDPE GEOMEMBRANE LINER SYSTEM 0	2 3 4 5
05 06	PART I	- GENERAL 0	6 7
07 08	1.01 S	UMMARY 0.	, 8 9
09 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 27 29 30		Section Includes: 1. Furnish all labor, materials, tools, equipment, and perform all work and services necessary for or incidental to the furnishing and installation, complete, of an impermeable, HDPE geomembrane liner as shown on drawings and specified in accordance with provisions of the Contract Documents. 2. Completely coordinate work with that of all other trades. 3. Work items in project include, but are not necessarily limited to, the liner for the landfill lateral expansion. 4. Although such work is not specifically shown or specified, all supplementary or miscellaneous items, appurtenances, and devices incidental to or necessary for a sound, secure, complete, and compatible installation shall be furnished and installed as part of this work. 5. Furnish CQC Consultant to monitor work of Geomembrane Installer and to perform CQC testing in accordance with provisions of the Contract Documents. 6. The Contractor, Geomembrane Installer, and CQC Consultant are required to attend the CQA/CQC Resolution Meeting and the CQA/CQC Preconstruction Meeting, Section 01200.	012345678901234567890
31 32 33 34 35	*3 · B.	Related Sections include but are not necessarily limited to: 1. Section 02220 - Earthwork. 2. Section 02221 - Trenching, Backfilling and Compacting. 3. Section 02240 - Leachate Collection System 4. Section 02276 - Soil Liner System.	31 32 33 34 35
36 37	1.02	QUALITY STANDARDS 3	36 37
38 39 40 41 42 43 44 45 47 49 51 52		Referenced Standards: 1. American Society for Testing and Materials (ASTM). a. ASTM D-638 Standard Test Method for Tensile Properties of Plastics b. ASTM D-751 Standard Test Method for Coated Fabrics c. ASTM D-792 Standard Test Method for Density and Specific Gravity (Relative Density) of Plastics by Displacement d. ASTM D-1004 Standard Test Method for Initial Tear Resistance of Plastic Film and Sheeting e. ASTM D-1238 Standard Test Method for Flow Rates of Thermoplastics by Extrusion Plastometer f. ASTM D-1603 Standard Test Method for Carbon Black in Olefin Plastics	389 1123 145 145 149 150 150
53			53

```
01
                    Subpart 2.02 for property to be tested.
01
                                                                                    02
               National Sanitation Foundation (NSF) Standard No. 54.
02
                                                                                    03
               The Geosynthetic Research Institute (GRI).
03
                                                                                    04
                   GRI GM5(a) Notched Constant Tensile Load (NCTL) Test for
04
                                                                                    05
                    Polyolefin Geomembranes
05
                                                                                    06
                   GRI GM6 Pressurized Air Channel Test for Dual Seam
06
                                                                                    07
                    Geomembranes.
07
                                                                                    08
               The accompanying CQA Plan, prepared by HDR Engineering.
08
                                                                                    09
09
                                                                                    10
           Qualifications:
10
       В.
                                                                                    11
               Each geomembrane Manufacturing or Installation firm shall
11
                                                                                    12
               demonstrate 5 years continuous experience, including a minimum
12
                                                                                    13
                of 10,000,000 SF of HDPE geomembrane manufacture or instal-
13
                                                                                    14
14
                Geomembrane Installer Personnel Qualifications: Installation
                                                                                    15
15
           2.
                Superintendent shall have worked in a similar capacity on at
                                                                                    16
16
                least five HDPE geomembrane liner jobs similar in size and
                                                                                    17
17
                complexity to the project described in the Contract Documents.
                                                                                    18
18
                                                                                    19
                The Master Welder shall have completed a minimum of 5,000,000
19
                square feet of HDPE geomembrane seaming work using the type
                                                                                    20
20
                of seaming apparatus proposed for use on this Project. Other
                                                                                    21
21
                welders shall have seamed a minimum of 1,000,000 square feet
                                                                                    22
22
                                                                                    23
                of HDPE geomembrane.
23
                                                                                    24
                The CQC Consultant shall meet the qualification requirements
24
                                                                                    25
                of Section 01410 of these Specifications.
25
                                                                                    26
26
                                                                                    27
            COA PLAN IMPLEMENTATION - Construction Quality Assurance for the
27
            HDPE geomembrane installation will be performed for the Owner by
                                                                                     28
28
                                                                                     29
            the CQA Consultant in accordance with the CQA Plan prepared for
 29
            this project. The work performed under the CQA Plan is paid for
                                                                                     30
 30
            by the Owner and is not a part of this contract. The Contractor,
                                                                                     31
 31
                                                                                     32
            CQC Consultant, and Geomembrane Installer, however, should
 32
                                                                                     33
            familiarize themselves with the CQA Plan and are responsible for
 33
            providing reasonable notice of and access to work elements that
                                                                                     34
 34
                                                                                     35
            the CQA Consultant is required by the CQA Plan to overview.
 35
                                                                                     36
 36
                                                                                     37
     1.03 SUBMITTALS
 37
                                                                                     38
 38
                                                                                     39
            Submit for Engineer's approval prior to placement of geomembrane
 39
                                                                                     40
            liner, including:
 40
                                                                                     41
                Manufacturer's Submittals.
 41
                                                                                     42
                    Manufacturer's Quality Control (MQC) Program: Submit for
 42
                                                                                     43
                     review a complete description of the geosynthetic Manufac-
 43
                     turer's formal quality control program for manufacturing
                                                                                     44
 44
                                                                                     45
                     HDPE geomembrane. The MQC program shall include as a
 45
                                                                                     46
 46
                     minimum:
                                                                                     47
                         Testing of incoming resin prior to manufacture of
 47
                                                                                     48
                         geomembrane at a frequency of not less than one per
 48
                         hopper. This testing shall include the following tests
                                                                                     49
 49
                                                                                     50
 50
                         and minimum criteria:
                                                                                     51
                             Specific Gravity (ASTM D792 Method A or ASTM
 51
                                                                                     52
                                      >0.935.
                             D1505):
 52
                             Melt Index (ASTM D1238 Condition 190/2.16):
                                                                                     53
 53
```

11.

. 12

1.0g/10 min.

2) Routine testing of the manufactured sheet for physical parameters to confirm that the geomembrane meets or exceeds these Specifications (2.02 A.4). Testing for carbon black content and dispersion, tensile strength, and elongation properties shall be at a frequency of not less than one per 40,000 SF of geomembrane. Testing for environmental stress crack resistance shall be at a frequency of not less than one per 400,000 SF of geomembrane. Thickness shall be monitored continuously through the manufacturing process, or measured physically at a frequency of not less than once per 1,000 SF of geomembrane.

3) Extrusion rod. Extrusion rod shall be manufactured from identical resin to that used in geomembrane manufacture. Manufactured extrusion rod shall be tested for carbon black content and dispersion, specific gravity and melt index at a frequency of not less than one test per batch.

4) The Manufacturer shall reject resin and geomembrane that do not conform with the requirements of the approved MQC program.

- 5) MQC data shall accompany the geomembrane shipment.
 b. Manufacturer's Field Installation Procedures Manual:
 Submit complete geomembrane Manufacturer's specifications, descriptive drawings, and literature for the recommended installation of the HDPE geomembrane liner system, including recommended methods for handling and storage of all materials prior to installation, and field installation guidelines that the manufacturer feels are relevant and important to the success of this project. At a minimum, the manual shall include the following provisions with exceptions noted by the Manufacturer:
 - Geomembrane shall not be placed upon standing water or other conditions which will result in deterioration of the CSL.
 - 2) The Geomembrane Installer shall remove any materials placed to protect the CSL prior to placement of the geomembrane liner.
 - 3) Adjacent rolls of geomembrane shall overlap a minimum of 4 IN.
 - 4) Geomembrane liner shall be handled and placed in a manner which minimizes wrinkles, scratches, and crimps.
 - 5) Geomembrane liners shall be welded using either extrusion or radiant wedge welding equipment. Each piece of welding equipment and each operator shall perform demonstration welds at the start of a shift, whenever equipment is switched on, and at other times at the discretion of the CQC Consultant. These demonstration welds shall be tested using daily record that summarizes panels deployed, seams completed, seam testing, seam repair, personnel on site, and equipment on site using field tensiometer and, at a minimum,

01		exhibit seam shear strength of greater than 128 LBS per 01
02		inch of width (smooth), 113 lbs per inch of width 02
03		(textured) and seam peel shear strength of greater 03
04		than 98 LBS per inch of width (smooth), 88 lbs per inch 04
05		of width (textured).
06		Surfaces to be welded shall be clean and dry at the 06
07		time of welding. Geomembrane shall not be welded when 07
08		ambient temperatures are below 40 Deg F (5 Deg C) or 08
09		above 104 Deg F (40 Deg C) unless the Geomembrane 09
10		installer can demonstrate that the seam quality is not 10
11		compromised.
12		(7) Geomembrane liners shall be welded continuously without 12.
13		fishmouths or breaks in the weld. Where fishmouths are 13
14		unavoidable, the geomembrane sheet shall be slit to a 14
15		point such that the sheet lies flat and with no 15
16		remaining wrinkle. The two edges of the slit shall be 16
17		welded together provided that the overlap for this weld 1/
18		shall be a minimum of 3 IN. Areas of the slit which do 18
19		not achieve an overlap of 3 IN, including the terminus 19
20		of the slit, shall be provided with a patch as 20
21		discussed below.
22		8) Defects in and damage to geomembrane sheets shall be 22
23		repaired by welding a patch over the defect using 23
24		extrusion welding equipment. The patch material shall 24
25		consist of an undamaged piece of geomembrane cut to 25
		provide a minimum of 3 IN of overlap in all directions 26
27		from the defect. Torn or permanently twisted 2/
28		geomembrane shall be replaced at no expense to the 28
29		Owner. 29
30		 Personnel walking on the geosynthetic shall not engage 30
31		in activities or wear types of shoes, that could damage 31
32		the geosynthetic. Smoking shall not be permitted while 32
33		working on the geomembrane.
34		0) Vehicular traffic directly on the geosynthetic shall 34
35		not be permitted. Equipment shall not damage the 35
36	•	geosynthetic materials by handling, trafficking, leakage 36
37		of hydrocarbons, or any other means. The unprotected 37
38		geomembrane surface shall not be used as a work area, 38
39		for preparing patches, storing tools and supplies, or 39
40		other uses.
41	С.	Manufacturer's Material Data: Prior to shipment of 41
42		geomembrane, submit quality control certificates for each 42
43		roll demonstrating conformance with the requirements of 43
44		these Specifications. Submit statement of production dates 44
45		for the resin and the HDPE geomembrane for this work. 45
46	d.	Manufacturer's written acceptance of Geomembrane 46
47		Installer's qualifications for installation of the HDPE 47
48		geomembrane. 48
49	e.	Warranty: Submit a warranty signed by the Manufacturer. 49
50		The warranty shall be against manufacturing defects and 50
51		workmanship and against deterioration due to ozone, ultra- 51
52		violet, and other exposure to the elements, for a period of 52
53		20 years on a pro rata basis. The warranty shall be limited 53

```
01
                    to replacement of material, and shall not cover installation
01
                                                                                     02
02
                    of replacement geomembrane.
                                                                                     03
                Geomembrane Installer's Submittals.
03
                    The Geomembrane Installer will submit written documentation
                                                                                     04
04
                                                                                      05
                    that their personnel satisfy the qualifications of 1.02 B.
05
                                                                                      06
                    Geomembrane Installer's Construction Quality Control
06
                    Program: Submit for review a complete description of the
                                                                                      07
07
                                                                                      08
                    Geomembrane Installer's formal construction quality control
08
                                                                                      09
                    programs to include, but not be limited to, product
09
                    acceptance testing, installation testing, including both non-destructive and destructive quality control field
                                                                                      10
10
                                                                                      11
11
                                                                                      12
                    testing of the sheets and seams during installation of the
12
                    geomembrane, proposed methods of testing geosynthetic
                                                                                      13
13
                                                                                      14
                    joints and connections at appurtenances for continuity,
14
                    documentation and changes, alterations, repairs, retests,
                                                                                      15
15
                                                                                      16
16
                    and acceptance.
                                                                                      17
                    Geomembrane Installer's Installation Procedures Manual:
17
                                                                                      18
                    submit for approval the Installer's installation manual to
18
                                                                                      19
                    include: ambient temperature at which the seams are made,
19
                    control of panel lift up by wind, acceptable condition of
                                                                                      20
20
                                                                                      21
21
                    the subsurface beneath the geomembrane, quality and
                    consistency of the welding material, proper preparation of
                                                                                      22
22
                    the liner surfaces to be joined, cleanliness of the seam
                                                                                      23
23
                                                                                      24
                    interface (e.g., the amount of airborne dust and debris
24
                                                                                      25
                    present), and proposed details for connecting the HDPE
25
                                                                                      26
                    liner to appurtenances, i.e. penetrations of the contain-
26
                                                                                      27
                    ment facilities. The document shall include a complete
27
                                                                                      28
                    description of seaming by extrusion welding and hot-wedge
28
                                                                                      29
                    welding. The Geomembrane Installer's Installation Manual
29
                                                                                      30
                    will by reference include requirements of the Manufac-
30
                    turer's Installation Manual unless exceptions are noted and
                                                                                      31
31
                    approved by the Engineer. After this manual has been
                                                                                      32
32
                                                                                      33
                    approved by the Engineer, the Geomembrane Installer shall
33
                    not deviate from the procedures included in the manual.
                                                                                      34
34
                                                                                      35
                    Geomembrane panel layout with proposed size, number,
35
                    position and sequencing of panels and showing the location
                                                                                      36
36
                                                                                      37
37
                    and direction of all field joints.
38
                    Warranty: The Geomembrane Installer shall agree in writing
                                                                                      38
                    to warranty the geomembrane system to be free of defects
                                                                                      39
39
                     for a period of 2 years following the date of acceptance
                                                                                      40
40
                                                                                      41
41
                     of the work performed under this contract.
                                                                                      42
42
                COC Consultants Submittals:
                                                                                      43
43
                    CQC Consultant shall submit written documentation that
                                                                                      44
44
                     their personnel satisfy the qualifications of Section
                                                                                      45
45
                                                                                      46
46
                    COC Consultants COC Geomembrane Manual: Submit CQC
47
                     Consultant's written program for meeting the geomembrane
                                                                                      47
                     material conformance and CQC requirements of these
                                                                                      48
48
                                                                                      49
49
                     Specifications.
                Provide all submittals in a single coordinated transmittal.
                                                                                      50
50
                                                                                      51
                Partial submittals will not be accepted. All submittals must
51
                be submitted prior to the Geomembrane Preconstruction Meeting,
                                                                                      52
52
                                                                                      53
53
                Section 01200.
```

structures or practices.

precipitation falling within the area or from inadequate diversion

The Contractor shall be responsible to coordinate the installation of the leachate collection system which shall be in accordance with Geomembrane Installer's Installation Manual and as specified in these Specifications and shown on the Contract Drawings. E. Vehicles will not be allowed on the liner area unless at least 24 inch (24") of cover has been placed over the liner except as noted in these Specifications. Vehicles larger than one and one-half ton pick up trucks are prohibited on the exterior berms. Contractor shall repair any 1.1 damage to exterior berms prior to final payment. 1.05 DEFINITIONS Geomembrane Manufacturer: Manufacturer of geomembranes produces geomembrane sheets from resin and additives. The manufacturer is responsible for producing geomembrane sheet which complies with these Specifications. These responsibilities include but are not limited to: 1. Acceptance of the resin and additives from chemical formulators. Testing of the raw resin and additives to ensure compliance with the manufacturer's specifications and with this Specification. Formulation of the resin and additives into geomembrane sheeting using mixing and extrusion equipment. Testing of the geomembrane sheet to ensure compliance with manufacturer's specification and this Specification. Shipping of the geomembrane sheet to Installer designated facilities. Certification of the raw materials and finished geomembrane sheet to comply with this Specification. Certification of installer's training, experience, and methods for welding and inspection geomembrane installations in compliance with manufacturer's standards. Installer of geomembranes are responsible Geomembrane Installer. for handling, fitting, welding and testing of geomembrane sheets or blankets in the field. These responsibilities include but are not limited to: 1. Acceptance (in writing) of the geomembrane from the manufacturer. Acceptance (in writing) of the CSL surface which will serve as a base for the geomembrane. This acceptance shall precede installation of the geomembrane, and shall state that the installer has inspected the surface, and reviewed the Specifications for material and placement, and finds all conditions acceptable for placement of geomembrane liners. The written acceptance shall explicitly state any and all exceptions to acceptance. Handling, welding, testing, and repair geomembrane liners in compliance with this Specification and the Geomembrane Installer's Installation Procedures Manual. 4. Performance of QA/QC testing and record keeping as required

Geomembrane liners shall consist of unsupported polyethylene

in thickness as shown on Drawings and manufactured from virgin,

01 02 03 04 05 06 07 08 09 10 11 12 13 14 15 16 17 18 19 20	 3. 4. 	first quality resin designed and formulated specifically for liquid containment in hydraulic structures. Reclaimed polymer shall not be added to the resin; except use of polymer recycled during the manufacturing process shall be allowed provided that recycled polymer shall be clean and shall not exceed 2 percent by weight. The geomembrane liner shall be manufactured to be free of holes, blisters, undispersed raw materials, or any sign of contamination by foreign matter. Any such defects shall be cause for rejection of the defective geomembrane material. Minor defects may be repaired in accordance with manufacturer's recommendations if this repair is approved by the Engineer. The geomembrane liner shall be manufactured as seamless rolls or as prefabricated panels with a minimum width of 22 FT as delivered to the site. All factory seams shall be inspected and tested for strength and continuity prior to delivery to the site. Geomembrane liner material shall possess properties which meet or exceed the following minimum requirements:						
21				TEST V	ALUE	20 21		
22 23 24		PROPERTY	TEST METHOD	SMOOTH HDPE	TEXTURED HDPE	22 23 24		
25		======	=========	=======================================	=========	25 26		
26 🕾 27 28 29		 Sheet Thickness, Mils 	ASTM D751	57 to 63	57 to 63	27 28 29		
30 31 & 32 33		 Density (g/cc) (Minimum prior to Carbon Black) 	ASTM D1238	0.934	0.934	30 31 32 33		
34 35 36 37		Melt Flow Index g/10 min.	ASTM D1238 Condition 190/2.16	0.30-1.00	0.3-1.00	34 35 36 37		
38 39 40 41 42		4. Minimum Tensile Properties	ASTM D638, Type IV, Dumb-bell at 2 ipm.(Each direction)			38 39 40 41 42		
43 44 45 46		a. Min. Tensile Strength at Break		240	75	43 44 45 46		
47 48 49 50		(lbs/inch) b. Min. Tensile Strength at Yield		140	140	47 48 49 50		
51 52 53		(lbs/inch) c. Min. Elongation at Break		700	150	51 52 53		

01 02 03 04			(Percent) d. Min. Elongation at Yield (Percent)		13	13	01 02 03 04 05
05 06 07 08		5.	Min. Tear Resistance Initiation (lbs)	ASTM D1004 Die C	45	45	05 06 07 08 09
09 10		6.	Carbon Black	ASTM D1603	2.00-3.00	2.00-3.00	10 11
11 12 13	•	7	Carbon Black Dispersion	ASTM D3015	A1 .	A1 .	12 13 14
14 15 16 17		8.	Min. Environmental Stress Crack Resistance (hrs)	ASTM D1693 Condition C	1500	1500	15 16 17 18
18 19 20 21 22		9.	Notched Constant Load Test	GRI GM5	Transition Time >100 Hrs @ 35% Yield	Transition Time >100 Hrs @ 35% Yield	19 20 21 22 23
23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 40 41 42 43 44 45 46 47 48		du 6. Pr th co Th pa a. b. 7. Th	additives or filler ring manufacture of ior to shipment, the e Project Manager ar ntrol certificate fo e quality control ce rty employed by the roll numbers and i the results of qua- ee CQC Consultant wil- en received for each coperties meet the re-	the geomembrane Mand the CQC Consider the CQC Constant of the CQC CQC CONSTANT of the CQC CQC CQC CQC CQC CQC CQC CQC CQC CQ	e. anufacturer waltant with a geomembrane personance by nufacturer and and ests. a control ceratified	ill provide quality provided. a responsible d will include: tificate has d roll	24 25 26 27 28 29 30 31 32 33 34 35
	2.03 A.	with t contin wedge temper temper adequa	ng Equipment: Extrusthermocouples and tended to the second second to the second	mperature reado temperature of hall be provide es which contin Equipment sha delaying work,	ut devices wh the extrudate d with thermo uously monito ll be maintai and shall be nt voltage un	ich . Radiant couples and r the ned in supplied by a der a combined-	37 38 39 40 41 42 43 44 45 46 47 48
49 50 51 52 53	В.	tension	Tensiometer: The Ge ometer for on site s ensiometer shall be IV, 2 ipm) specific	hear and peel t in good working	esting of geo order, built	membrane seams. to ASTM D638	50

recent calibration. The tensiometer shall be motor driven and be equipped with a gauge that measures the force in unit pounds exerted between the jaws as displayed on a digital readout. Vacuum Box: The Geomembrane Installer shall provide a minimum of 2 vacuum box assemblies consisting of a rigid housing, a transparent viewing window, a soft closed cell neoprene gasket attached to the bottom, a port hole or valve assembly, a vacuum gauge, a vacuum pump assembly equipped with a pressure control, a rubber pressure/vacuum hose with fittings and connections, and a soapy solution and an applicator. The equipment shall be capable of inducing and holding a 1.1 minimum vacuum of 5 psi. Air Pressure Test: The Geomembrane Installer shall provide the necessary air pump and fittings required to perform the GRI GM6 air pressure test on dual seams. Roll Handling Equipment: The Geomembrane Installer shall provide handling equipment that is adequate and does not pose a risk to the geomembrane rolls. The CQC Consultant shall inspect the equipment and confirm its adequacy. PART 3 - EXECUTION 3.01 LINER SYSTEM CONSTRUCTION Compacted Soil Liner (CSL) Component: The CSL component shall be constructed in accordance with Section 02276 and the Contractor shall protect the CSL from freezing, desiccation, flooding with water, and freezing. Prior to placement of the geomembrane, the CSL must be prepared as follows: Lines and grade must be verified by a Licensed Land Surveyor; The surface must be proofrolled to verify the supporting b. soil condition: The surface must be inspected for rocks larger than 0.75 c. IN: and Steel drum rolled in preparation for the geomembrane. CSL acceptance: Geomembrane liner materials shall not be placed until the required CSL preparation has been completed and the CSL has been accepted and certified in writing by the Geomembrane Installer and approved by the CQA Engineer. В. Geomembrane Liner: The geomembrane liner shall be manufactured in accordance with the approved MQC program. The Manufacturer shall not deviate from the program without written approval of the Engineer. Transportation and handling of the geomembrane shall meet the following requirements: Transportation of the geomembrane is the responsibility of

the Geomembrane Installer, Contractor, or other party as

01			uqi ccu aponi)1)2 /
02	•			03 (
03 04 05			c. The CQC Consultant will verify that the handling equipment used on the site is adequate and will not damage the)4)5
06 07 08 09 10			geomembrane. d. Upon delivery to the site, the Geomembrane Installer and the CQC Consultant will conduct a surface examination of all rolls for defects or damage. This inspection will be conducted without unrolling rolls. The CQC Consultant will ensure that defective rolls are rejected and removed from	06 07 08 09 10 11
12 13 14 15 16 17		٠	e. The Geomembrane Installer will be responsible for the storage of the geomembrane on site. The Project Manager will provide a storage location on site. The Geomembrane Installer shall ensure that the storage space is adequate to protect the geomembrane from theft, vandalism,	13 14 15 16 17
· 18 19		3.		19
20		٠.	Consultant will perform conformance testing of the manufactured	20
21			geomembrane as follows:	21
22				22
23			wild in its the the second contract to the con	23 24
24			to ensure conformance to these Specifications and the manufacturer's list of guaranteed properties. As a minimum,	25
25				26
26 27				27
28				28
29				29
30				30
31			5) Tensile strength: ASTM D368	31
32			b. All test results shall be available at the site prior to	32
33				33
34			or campion with an entering the	34
35			did till too thereas one tries the tries to	35
36	•		College with the man is the meaning and	36
37				37 38
38	,		d bollier mande seems that a seem to be a se	39
39 40			 The Geomembrane Installer will replace the roll of geomembrane that is in nonconformance with a roll in 	40
41			conformance with these Specifications.	41
42			2) The Geomembrane Installer will remove conformance	42
43			samples for testing by the Geosynthetics CQC Laboratory	43
44			from the closest numerical roll on both sides of the	44
45			failed roll. These two samples must conform to these	45
46			Specifications. If either of these samples fail, then	46
47			the next numerical roll will be tested until a passing	47
48			roll is found.	48
49		4.	Field Panel Identification: The CQC Consultant will document	49
50			that the Geomembrane Installer labels each field panel with an	50
51			"identification code" consistent with the approved panel layout	51 52
52			plan. The location of the label and the color of marker used must be as agreed to in the QA/QC Preconstruction Meeting.	53
53			must be as agreed to in the VM/VC rreconstruction meeting.	

01 02 03 04 05 06 07 08 09 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 27 28 30 31 31 32 33 34 35 36 37	 6. 	Geomembrane installation: Geomembrane in accordance with the approved of Installation Procedure Manual and Geomembrane Installer shall maint drawing showing the location of a Geomembrane Testing (Non-destruct Installer shall test and document using one of the following nondes a. Vacuum testing shall conform Brush soapy solution on geome over the wetted seam area. It is created. Apply a pressure Examine the geomembrane throup resence of soap bubbles for seconds. All areas where some marked and repaired as described. Air Pressure Testing (for document space) shall conform to GRI (Destructive Testing: The Geomembrase destructively at a minimum soon LF of weld. Destructive test be performed by the CQC Consultant Laboratory. The CQC Consultant destructive test samples. Conform by the CQA Consultant in accordance. The destructive sample shall long with the seam centered be cut into three (3) equal geomembrane Installer, the CC Consultant. b. All tests shall exhibit a Fit separation in which the geomembrane in which the geomembrane weld. At least 5 coupons method. Five of five coupons requirements, as specified be	Geomembrane Inside panel layout tain a weekly used in the Geometral seam weld structive seam to the following of the seam with the property of other seam with the property of the seam with the property of other seam with the property of other seam with the property of other with the propert	taller's Field drawing. The pdated as-built s. embrane s continuously tests: ng procedure: vacuum box eak-tight seal ely five (5) psi. window for the fifteen (15) ar shall be ction. an enclosed s. shall field test ne test per amples shall also C Geosynthetics the location of fill be performed oject CQA Plan. Fide by 42 inches the sample shall fibution to the find the CQA type of l tears before fill tears before	13 14 15 16 17 18 19 20					
38 39 40		Description	Test Method =====	(lbs/in width)	37 38 39 40					
41 42 43 44 45		60 mil Smooth HDPE Shear 60 mil Textured HDPE Peel	ASTM D-413 ASTM D-816 ASTM D-413 ASTM D-816	98 126 88 113	41 42 43 44 45					
46 47 48 49 50 51 52	8.	Documentation: The following do at the project site for review by Consultant: a. Geomembrane Installer's Document of the consultant of th	y the Project M mentation: that summarize sting, seam rep ite.	danager or CQA es panels deployed, pair, personnel on	46 47 48 49 50 51 52 53					

01				subgrade acceptance for each panel deployed.	UΙ
02			3)	Seam Testing Log: provides a complete record of all	02
03			- ,	nondestructive and destructive seam tests performed as	03
04				part of the Geomembrane Installer's QC program.	04
05			4)	Seam/Panel Repair Log: provides a complete record of	05
06			• 7	all repairs and vacuum box testing of repairs made to	06
07				defective seams or panels.	07
08			5)	As-built Drawing: maintain an as-built drawing updated	80
09			-,	on a weekly basis.	09
10		· b.	COC	Consultant's Documentation	10
11			1)	Daily Log: daily record that summarizes panels deployed,	11
12			-,	seams completed, CQC seam testing, seam repair,	12
13		-		personnel on site, equipment on site, weather	13
14				conditions, etc.	14
15			2)	CQC Testing Log: record of all seam destructive tests	15
16			-,	and material conformance tests performed by the CQC	16
17				Geosynthetics Laboratory.	17
18			3)	Material Conformance: maintain original conformance	18
19			•	certificate(s) from geomembrane manufacturer.	19
20			4)	Subgrade Acceptance Log: maintained originals of	20
21			,	subgrade acceptance forms for each panel and signed by	21
22				the Geomembrane Installer.	22
23					23
24	3.02	GEOMEMBR	RANE .	ACCEPTANCE	24
25					25
26	Α.	The Geo	memb	rane Installer shall retain all Ownership and responsi-	26
27		bility	for	the geomembrane liner system until final acceptance by	27
28		the Owr	ier.	Owner will accept the geosynthetic installation when	28
29		the ins	stall	ation is finished and all required submittals from the	29
30		Geomemb	orane	Installer and CQC Consultant have been received and	30
31		approve	ed, a	nd CQA verification of the adequacy of all field seams	31
32		and rep	airs	, including associated testing, is complete.	32
33		•			33
34					34
35				END OF SECTION	35

01		SECTION 02800	01
02 03 04 05		GEOSYNTHETIC CLAY LINER (GCL)	02 03 04 05
06 07	PART 1	- GENERAL	06 07
08 09	1.01	SUMMARY	09
10 11 12 13 14 15 16 17 18 19 20 21 22 23	Α.	 Section Includes: Furnish all labor, material, and equipment to complete installation of the GCL in accordance with the Contract Drawings and these Specifications. Completely coordinate work with that of other trades. Although such work is not specifically shown or specified, all supplementary or miscellaneous items, appurtenances, and devices incidental to or necessary for a sound, secure, complete, and compatible installation shall be furnished and installed as part of this work. Furnish CQC Consultant to monitor the work of GCL Installer and to perform CQC testing in accordance with provisions of the Contract Documents. 	10 11 12 13 14 15 16 17 18 19 20 21 22 23
24 25 26 27		Related Sections include but are not necessarily limited to: 1. Section 02220 - Earthwork. 2. Section 02775 - HDPE Geomembrane Liner.	24 25 26 27
28 29	1.02	QUALITY STANDARDS	28 29
29 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45		Referenced Standards: 1. American Society for Testing and Materials (ASTM). a. ASTM D 1777, Method for Measuring Thickness of Textile Materials. b. ASTM D 3776, Test Methods for Weight (mass) per Unit Area of Woven Fabric. c. ASTM D 4632, Test Method for Grab Breaking Load and Elongation of Geotextile. d. ASTM D 4833, Test Method for Index Puncture Resistance of Geotextiles, Geomembranes, and Related Products. e. ASTM D 5084, Test Method for Hydraulic Conductivity of Saturated Porous Materials Using a Flexible Wall Permeameter. f. ASTM D 5321, Test Method for Determining the Coefficient of Soil and Geosynthetic or Geosynthetic and Geosynthetic Friction by the Direct Shear Method.	30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46
46 47 48 49 50	В.	Qualifications: 1. Manufacturer: The GCL shall be furnished by a Manufacturer that has previously produced a minimum of 1,000,000 square feet of the material for use in similar projects.	47 48 49 50
51 52 53	С.	CQA Plan Implementation: Construction Quality Assurance documentation for the GCL installation will be performed for the	51 52 53

Owner by the CQA Consultant in accordance with the CQA Plan prepared for this project. The work performed under the CQA Plan is paid for by the Owner and is not a part of this contract. The Contractor, COC Consultant, and GCL Installer, however, should familiarize themselves with the CQA Plan and are responsible for providing reasonable notice of and access to work elements that the CQA Consultant is required by the CQA Plan to overview.

SUBMITTALS 1.03

- Pre-Installation: The Contractor shall submit the following information and material to the CQA Consultant prior to installation: 12 of the GCL.
 - Product Data and Factory Test Results: Published product properties and specifications for the proposed GCL, as well as factory test results of materials certified by the GCL manufacturer shall be submitted showing conformance with the requirements of these Specifications. In addition, the Contractor shall submit the Manufacturer's certification stating that the material is similar to and of the same formulation as that for which test results are submitted, and by which actual usage has been demonstrated to be satisfactory for the intended application.
 - Samples: Samples of the GCL sheeting shall be provided to the 2. COA Consultant. Samples shall have a width of 6 inches, and a length of 8 inches.
 - Delivery, Storage, and Handling Instructions: The Manufacturer's recommendations for delivery, storage, and handling shall be submitted to the CQA Consultant for review.
 - Delivery Date: The CQA Consultant shall be notified of the scheduled delivery date for the materials.
 - Installation Drawings, Procedures, and Schedules: Installation drawings, procedures, and a schedule for carrying out the work shall be provided by the Contractor to the CQA Consultant for Procedures addressed by the Contractor shall include but not be limited to material unloading, storage, installation, repair, and protection to be provided in the event of rain. A schedule showing the order of placement, location of panels, seams, and penetrations shall be submitted for the COA Consultant's review. Submit drawings showing the panel layout, seams, and associated details including pipe penetrations. Following review, these drawings will be used for installation of the GCL. Any deviations from these drawings must be approved by the CQA Consultant.
- Post-Installation: Upon completion of GCL installation the Contractor shall submit the following to the CQA Consultant:
 - A certificate stating that the GCL has been installed in accordance with the Plans, Specifications, and the Manufacturer's recommendations.
 - Manufacturer's Warranty: The material warranty shall be for defects or failures related to manufacture on a non-prorata basis for five (5) years after date of shipment.

	01 02 03 04 05 06 07 08 09 10		 GCL Installer's Warranty: The GCL Installer's warranty shall warrant their workmanship to be free of defects on a non-prorata basis for five (5) years after the final acceptance of the Work. This warranty shall include but not be limited to overlapped seams, anchor trenches, attachments to appurtenances, and penetration seals. Record Drawing Information: Record drawings including but not limited to drawings showing the location of all seams, panels, repairs, patches, anchor trenches, pipe penetrations, and other appurtenances, including measurements and dimensions, shall be prepared by the Contractor and submitted to the CQA Consultant following completion of the project. 	01 02 03 04 05 06 07 08 09 10
• •	13 14	1.04	PROJECT CONDITIONS	13 14
	15 16 17 18 19 20 21 22	A. B.	The GCL shall not be placed in standing water, high humidity, or while raining. Any material that becomes partially or completely hydrated in the opinion of the CQA Consultant shall be removed and replaced at Contractor's expense. Take necessary precautions to protect underlying soil and geomembrane liners from damage due to any construction activity.	15 16 17 18 19 20 21 22
	23		Damage to liners shall be repaired at Contractor expense.	23
	24			24
	25 26	PART :	2 - PRODUCTS	25 26
3 mm	27	1711(1		27
	28	2.01	MATERIALS	28
75 (44.51)			· · · · - · · - · · · · · · · · · · · ·	
Televisión (*)	29	\mathcal{P}		29
*	30		General:	29 30
	30 31 32 33 34 35	<i>∜</i> ↓ A.	General: 1. The GCL shall consist of bentonite encased, front and back, with geotextile. GCL consisting of bentonite backed with geomembrane can be used only if approved by the Project Manager and Engineer. The materials supplied under these Specifications shall be first quality products designed and manufactured	29 30 31 32 33 34 35
	30 31 32 33 34 35 36	# A.	General: 1. The GCL shall consist of bentonite encased, front and back, with geotextile. GCL consisting of bentonite backed with geomembrane can be used only if approved by the Project Manager and Engineer. The materials supplied under these Specifications shall be first quality products designed and manufactured specifically for the purposes of this work.	29 30 31 32 33 34 35 36
	30 31 32 33 34 35 36 37	# A.	 General: 1. The GCL shall consist of bentonite encased, front and back, with geotextile. GCL consisting of bentonite backed with geomembrane can be used only if approved by the Project Manager and Engineer. The materials supplied under these Specifications shall be first quality products designed and manufactured specifically for the purposes of this work. 2. The GCL shall be supplied in rolls which have a minimum width 	29 30 31 32 33 34 35 36
	30 31 32 33 34 35 36 37 38 39	# A.	 General: 1. The GCL shall consist of bentonite encased, front and back, with geotextile. GCL consisting of bentonite backed with geomembrane can be used only if approved by the Project Manager and Engineer. The materials supplied under these Specifications shall be first quality products designed and manufactured specifically for the purposes of this work. 2. The GCL shall be supplied in rolls which have a minimum width of 12 feet. The roll length shall be maximized to provide the largest manageable sheet for the fewest overlaps. Labels on 	29 30 31 32 33 34 35 36
	30 31 32 33 34 35 36 37 38 39 40	# A.	 General: The GCL shall consist of bentonite encased, front and back, with geotextile. GCL consisting of bentonite backed with geomembrane can be used only if approved by the Project Manager and Engineer. The materials supplied under these Specifications shall be first quality products designed and manufactured specifically for the purposes of this work. The GCL shall be supplied in rolls which have a minimum width of 12 feet. The roll length shall be maximized to provide the largest manageable sheet for the fewest overlaps. Labels on the roll shall identify the sheet number, date of fabrication, 	29 30 31 32 33 34 35 36 37 38 39 40
	30 31 32 33 34 35 36 37 38 39 40 41	# A.	 General: The GCL shall consist of bentonite encased, front and back, with geotextile. GCL consisting of bentonite backed with geomembrane can be used only if approved by the Project Manager and Engineer. The materials supplied under these Specifications shall be first quality products designed and manufactured specifically for the purposes of this work. The GCL shall be supplied in rolls which have a minimum width of 12 feet. The roll length shall be maximized to provide the largest manageable sheet for the fewest overlaps. Labels on the roll shall identify the sheet number, date of fabrication, proper direction of unrolling, and minimum recommended overlap. 	29 30 31 32 33 34 35 36 37 38 39 40
	30 31 32 33 34 35 36 37 38 39 40 41 42	# A.	 General: The GCL shall consist of bentonite encased, front and back, with geotextile. GCL consisting of bentonite backed with geomembrane can be used only if approved by the Project Manager and Engineer. The materials supplied under these Specifications shall be first quality products designed and manufactured specifically for the purposes of this work. The GCL shall be supplied in rolls which have a minimum width of 12 feet. The roll length shall be maximized to provide the largest manageable sheet for the fewest overlaps. Labels on the roll shall identify the sheet number, date of fabrication, proper direction of unrolling, and minimum recommended overlap. A quality control certificate shall be supplied with each roll. 	29 30 31 32 33 34 35 36 37 38 39 40 41 42
	30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45	# A.	 General: The GCL shall consist of bentonite encased, front and back, with geotextile. GCL consisting of bentonite backed with geomembrane can be used only if approved by the Project Manager and Engineer. The materials supplied under these Specifications shall be first quality products designed and manufactured specifically for the purposes of this work. The GCL shall be supplied in rolls which have a minimum width of 12 feet. The roll length shall be maximized to provide the largest manageable sheet for the fewest overlaps. Labels on the roll shall identify the sheet number, date of fabrication, proper direction of unrolling, and minimum recommended overlap. 	29 30 31 32 33 35 36 37 38 39 40 41 42 43 44 45
	30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48	# A.	 General: The GCL shall consist of bentonite encased, front and back, with geotextile. GCL consisting of bentonite backed with geomembrane can be used only if approved by the Project Manager and Engineer. The materials supplied under these Specifications shall be first quality products designed and manufactured specifically for the purposes of this work. The GCL shall be supplied in rolls which have a minimum width of 12 feet. The roll length shall be maximized to provide the largest manageable sheet for the fewest overlaps. Labels on the roll shall identify the sheet number, date of fabrication, proper direction of unrolling, and minimum recommended overlap. A quality control certificate shall be supplied with each roll. The GCL shall be reinforced where placed on slopes of 10H:1V or steeper. The GCL may be non-reinforced on slopes of less than 	29 30 31 32 33 34 35 36 37 38 40 41 42 43 44
	30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48	. A.	General: 1. The GCL shall consist of bentonite encased, front and back, with geotextile. GCL consisting of bentonite backed with geomembrane can be used only if approved by the Project Manager and Engineer. The materials supplied under these Specifications shall be first quality products designed and manufactured specifically for the purposes of this work. 2. The GCL shall be supplied in rolls which have a minimum width of 12 feet. The roll length shall be maximized to provide the largest manageable sheet for the fewest overlaps. Labels on the roll shall identify the sheet number, date of fabrication, proper direction of unrolling, and minimum recommended overlap. A quality control certificate shall be supplied with each roll. 3. The GCL shall be reinforced where placed on slopes of 10H:1V or steeper. The GCL may be non-reinforced on slopes of less than 10H:1V. Physical Properties: Physical properties of GCL shall be as shown	29 30 31 33 34 35 36 37 38 40 42 43 44 45 46 47 48

	in accordance wi	th these specificatio	ns.				
3.03	GCL ACCEPTANCE						
Α.	. The GCL Installer shall retain all ownership and responsibility for the GCL until final acceptance by the Owner. The Owner will accept the GCL installation when the installation is finished, all required submittals have been received and approved, and CQC/CQA verification of the adequacy of all field seams and repairs, including associated testing, is complete.						
	Ţ	ABLE 1: REQUIRED GO	L PROPERTIES.				
•			VALUE .				
	ROPERTY	TEST METHOD	REINFORCED	NON-REINFORCED			
Maximu	m Hydraulic tivity	ASTM D 5084 (@ 30 psi effective stress)	5x10 ⁻⁹ cm/s				
Minimu Conten	ım Bentonite nt	ASTM D 3776 (@ 20% moisture)	0.95 lb/sf	0.95 lb/sf			
Minimu Streng	ım Grab Tensile ıth	ASTM D 4632	88 lbs	75 1bs			
Minimu Resist	um Puncture cance	ASTM D 4833	100 1bs	80 1bs			
Minimu	um Shear Strength	ASTM D 5321	500 psf (When Hydrated)	50 psf			
Minimu	ım Free Swell	USP-NF-XVII	24 ml.	24 ml.			
Maximu Conter	um Moisture nt	ASTM D4643	30%	40%			
Sodium Conter		X-Ray Diffraction	90 (Typ.)	90 (Typ.)			
	•	END OF SECTION					

```
01
01
                                                                                      02
                                SECTION 02900
02
                                                                                      03
03
                                                                                      04
                              GEOTEXTILE FABRIC
04
                                                                                      05
05
                                                                                      06
06
                                                                                      07
    PART 1 - GENERAL
07
                                                                                      80
80
                                                                                      09
    1.01 SUMMARY
09
                                                                                      10
10
                                                                                      11
            Section Includes:
11
                Geotextile fabric for all uses as shown in drawings including
                                                                                      12
12
                                                                                      13
13
                but not limited to:
                                                                                      14
                    Cushion geotextile to protect geomembrane from #57 stone;
14
                    Separator geotextile between LCR and operational cover;
                                                                                      15
15
                    Protective geotextile when impregnated to limit flow into
                                                                                      16
16
                                                                                      17
17
                     LCR: and
                    Other - to suit field conditions
                                                                                      18
- 18
                                                                                      19
19
                                                                                      20
            Related Sections include but are not necessarily limited to:
20
                                                                                      21
21
                Section 02220 - Earthwork.
                                                                                      22
                Section 02775 - Geosynthetic Liner System.
22
                COA Plan.
                                                                                      23
23
                                                                                      24
24
                                                                                      25
           QUALITY STANDARDS
 25
     1.02
                                                                                      26
 26
                                                                                      27
 27
            Reference Standards:
                                                                                      28
                American Society for Testing and Materials (ASTM):
 28
                                                                                      29
 29
                     D3776, Test Method for Mass Per Unit Area of Woven Fabric.
                     D4354, Practice for Sampling of Geosynthetics for Testing.
                                                                                      30
 30
                     D4355, Test Method for Deterioration of Geotextiles from
                                                                                      31
 31
                                                                                      32
 32
                     Exposure to Ultraviolet Light and Water.
                                                                                      33
                     D4491, Test Method for Water Permeability of Geotextiles by
 33
                d.
                                                                                      34
                     Permittivity.
 34
                                                                                      35
                     D4632, Test Method for Grab Breaking Load and Elongation.
 35
                e.
                                                                                      36
                     D4751, Determining Apparent Opening Size of a Geotextile.
 36
                 f.
                                                                                      37
 37
                     D4833. Test Method for Index Puncture Resistance of
                                                                                      38
                     Geotextiles, Geomembrane, and Related Products.
 38
                     D4873, Guide for Identification, Storage, and Handling of
                                                                                      39
 39
                 h.
                                                                                      40
                     Geotextiles.
 40
                                                                                      41
 41
                                                                                      42
            Construction Quality Assurance Plan.
 42
                                                                                       43
 43
                                                                                       44
 44
     1.03 SUBMITTALS
                                                                                       45
 45
                                                                                       46
 46
            Shop Drawings:
        Α.
                                                                                       47
            1. See Section 01300.
 47
                                                                                       48
                 Product technical data.
 48
                                                                                       49
                Manufacturer's delivery, storage, handling, and installation
 49
                                                                                       50
                 instructions.
 50
                                                                                       51
 51
                                                                                       52
 52
     PART 2 - PRODUCTS
                                                                                       53
 53
```

01			01
02 03	2.01	ACCEPTABLE MANUFACTURERS	02 03
04 05 06	Α.	Subject to compliance with the Contract Documents, the following Manufacturers are acceptable: 1. Geotextiles:	04 05 06
07 08 09 10		a. Hoechst Celanese Corp.b. Advanced Drainage Systems Inc.c. Amoco Fabrics and Fibers Co.d. Or approved equal.	07 08 09 10
11 12	2.02	FABRICATION	11 12 13
13 14 15 16	Α.	Cushion Geotextile: Non-woven, needle punched; polyester or poly- propylene; continuous filament or staple fibers; conforming to the following properties:	14 15 16 17
17 18		Property or Test Method Required Value	18 19
19 20 21 22 23 24 25		Unit Weight (ASTM D3776)	20 21 22
	В	Separator Geotextile: Non-woven, needle punched; polyester or poly- propylene; continuous filament or staple fibers; conforming to the following properties:	23 24 25 26
26 27		Property or Test Method Required Value	27 28 (
28 29 30 31 32 33 34 35	,	Unit Weight (ASTM D3776) 6 osy (minimum) Grab Tensile Strength (ASTM D4632)	29 30 31 32 33 34 35
36 37 38		Alternative Separator Geotextile: Woven; polyester or polypropylene; conforming to the following properties:	36 37 38
39 40 41 42 43		Grab Tensile Strength (ASTM D4632)	39 40 41 42 43 44
44 45 46 47		Protective Geotextile: Nonwoven; polyester or polypropylene; continuous filament or staple fibers; conforming to the following properties:	45 46 47 48
48 49 50		Property or Test Method Required Value	49 50
51 52 53		Unit Weight (ASTM D3776) 6 osy (minimum) Grab Tensile Strength (ASTM D4632) 180 lb (minimum) Elongation (ASTM D4632)	51 52 53

```
Puncture Strength (ASTM D4833). . . . . . . . . . . 70 lb (minimum)
                                                                           01
01
          02
02
                                                                           03
03
                                                                           04
          Alternative Protective Geotextile: Woven; polyester or
04
                                                                           05
          polypropylene; conforming to the following properties:
05
                                                                           06
06
          Grab Tensile Strength (ASTM D4632) . . . . . . 180 lb (minimum)
                                                                           07
07
          08
08
          09
09
          10
10
                                                                           11
11
                                                                           12
12
                                                                           13
    PART 3 - EXECUTION
13
                                                                           14
14
                                                                           15
    3.01 INSTALLATION
15
                                                                           16
16
                                                                           17
17
          General Handling and Layout
                                                                            18
              General storage and handling of geotextiles must meet require-
18
                                                                            19
              ments of ASTM D-4873.
19
                                                                           20
              Exercise care when installing to prevent damage to geotextile.
20
              Lay out geotextile smooth and free of wrinkles, but loose enough
                                                                           21
21
                                                                            22
              that placement of overlying materials will not stretch or tear
22
                                                                            23
              the fabric.
23
                                                                            24
              Repair or replace geotextile that is torn or punctured. Repair
24
              by placing a geotextile patch over the damaged area, overlapping
                                                                            25
25
                                                                            26
              the existing geotextile by 12 IN (minimum) from any part of the
26
              damaged area. Repair or replace at no extra cost to Owner.
                                                                            27
27
                                                                            28
              Overlap rolls or sheets of geotextile 3 FT, minimum in the
28
                                                                            29
29
              longitudinal direction.
                                                                            30
              No equipment may operate directly on geotextiles. A minimum
30
              vertical separation of 9 IN must be maintained between all geo-
                                                                            31
31
                                                                            32
32
              textiles and equipment tracks or wheels.
                                                                            33
33
                                                                            34
34
          Seaming and Joining
                                                                            35
              Cushion: Join sheets without sewing but with a minimum of 4 IN
35
                                                                            36
              longitudinal overlap.
36
                                                                            37
37
              Separator: Join sheets with or without sewing or heat bonding.
                                                                            38
                  With Sewing: Overlap adjacent panels a minimum of 4 IN. Use
38
                  Type SSa (prayer) seam and a Type 401 stitch having a mini-
                                                                            39
39
                                                                            40
                  mum distance from the edge of the geotextile to the stitch
40
                                                                            41
                  line of 2.0 IN or follow recommendations of geotextile manu-
41
                                                                            42
42
                  With Heat Bonding: Overlap adjacent panels a minimum of 4 IN. 43
43
                                                                            44
                  Heat bond seam must develop a minimum of 60% of the tensile
44
                  strength of the parent geotextile as measured in ASTM D4632.
                                                                            45
45
                                                                            46
                  Without Sewing or Heat Bonding (Nonwoven only): Overlap
46
                                                                            47
47
                  adjacent rolls or sheets a minimum of 18 IN.
              Protective: Join sheets with sewing or heat bonding.
                                                                            48
48
                                                                            49
                  With Sewing: Overlap a minimum of 4 IN. Use Type SSa
49
                                                                            50
                  (prayer) seam and a Type 401 stitch having a minimum
50
                  distance from the edge of the geotextile to the stitch line
                                                                            51
51
                                                                            52
52
                  of 2.0 IN or follow recommendations of geotextile
                                                                            53
                  manufacturer.
53
```

01 02 03		Heat bond seam must develop a minimum of 60% of the tensile 0 strength of the parent geotextile as measured in ASTM D4632. 0	1 2 3 4
04 05 06 07 08 09	С.	Cushion Geotextile 1. Place geotextile directly on the geomembrane. 2. Prevent movement of LCR pipe and GT-C geotextile while placing stone 0	15 16 17 18 19
10 11 12 13 14 15 16 17	D.	Separator Geotextile 1. Place fabric directly on a relatively smooth subgrade, free of obstructions, abrupt depressions or humps, debris, or deposits of loose or soft soil. 2. Care must be taken to avoid damaging the Type GT-S geotextile during placement of the soil over the geotextile. This may require use of a thicker loose lift or a smooth drum roller to limit damage due to penetration of compactor feet.	.0 1.2 1.3 1.4 1.5 1.6 1.7 1.8
18 19 20 21 22 23 24 25 26 27 28 29 30 31	Ε.	Protective Geotextile 1. Place geotextile directly on #57 stone. 2. Place operational cover on either side of stone drain. 3. The Protective geotextile is tack coated after placement to limit future surface water infiltration. a. A cationic or anionic water based asphalt emulsion may be used as approved by the Engineer. b. Minimum air temperature shall be at least 50°F and rising for placement of the tack coat. c. The temperature of the tack coat shall be sufficiently high to permit a uniform spray pattern. To avoid damage to the geotextile, the maximum temperature shall not exceed 325°F. d. The application rate shall not be less than 0.20 gallons per square yard.	19 20 21 22 23 24 25 27 28 29 31 32 33
33 34 35	3.02	COC TESTING	34 35
36 37 38 39	· A.	The CQC Consultant shall confirm that the identification, storage, and handling of geotextiles is in accordance with ASTM D4873. Any deviation from this requirement will be reported to the Engineer.	36 37 38 39
40 41 42 43 44	В.	The CQC Consultant will examine all manufacturer's certifications to ensure that the property values listed on the certifications meet or exceed these specifications. Any deviations will be reported to the Engineer.	40 41 42 43
45 46 47 48 49	С.	Conformance Testing: The CQC Consultant shall sample the geotextiles in accordance with ASTM D4354. Sample will be sent to the CQC Geosynthetics Laboratory for the following conformance testing. Any deviations will be reported to the Engineer.	45 46 47 48 49
50 51 52 53		1. Cushion Geotextile Unit Weight (ASTM D3776) Grab Tensile Strength (ASTM D4632)	50 51 52 53

01		Unit Weight (ASTM D3776)	01
02		Grab Tensile Strength (ASTM D4632)	02
03		Elongation (ASTM D4632)	03
04		Puncture Strength (ASTM D4833)	04
05		Apparent Opening Size (ASTM D4751)	05
06		Permittivity (ASTM D4491)	06
07		3. Protective Geotextile	07
80		Unit Weight (ASTM D3776)	90
09		Grab Tensile Strength (ASTM D4632)	09
10		Elongation (ASTM D4632)	10
11	•	Puncture Strength (ASTM D4833)	1.1
12			- 12
13	D.	The CQC Consultant will observe placement of the geotextiles to	13
14		confirm that the panel overlaps and seams are in accordance with	14
15		these specifications. Any deviations will be reported to the	15
16		Engineer.	16
17			17
18		END OF SECTION	18

.

01	SECTION 02999	01
02 03 04	GEOCOMPOSITE DRAINAGE LAYER	02 03 04
05 06	PART 1 - GENERAL	05 06 07
07 08 09	1.01 SUMMARY	07 08 09
10 11 12 13 14 15	 A. Section Includes: Geocomposite drain for all uses as shown in drawings including but not limited to:	10 11 12 13 14 15
16 17 18 19 20 21 22 23 24	 B. Related Sections include but are not necessarily limited to: 1. Division 0 - Bidding Requirements, Contract Forms, and Conditions of the Contract. 2. Division 1 - General Requirements. 3. Section 02220 - Earthwork. 4. Section 02775 - HDPE Geomembrane Liner. 5. Section 02900 - Geotextile Fabric. 6. CQA Plan. 	16 17 18 19 20 21 22 23 24
25	1.02 QUALITY STANDARDS	25 26
26 27 28 30 31 33 34 35 36 37 38 40 41 42 43	A. Reference Standards: 1. American Society for Testing and Materials (ASTM): a. ASTM D1505, Standard Test Method for Density of Plastics by the Density-Gradient Technique. b. ASTM D792, Standard Test Methods for Density and Specific Gravity of Plastic by Displacement. c. ASTM D4716, Standard Test Method for Constant Head Hydraulic Transmissivity (In-Plane Flow) of Geotextiles and Geotextiles Related Products. d. ASTM D1777, Standard Method for Measuring Thickness of Textile Materials. 1.03 SUBMITTALS A. Shop Drawings: 1. See Section 01300. 2. Product technical data. 3. Manufacturer's delivery, storage, handling, and installation	27 28 29 30 31 32 33 34 35 36 37 38 40 41 42 43 44
44 45 46	 Manufacturer's delivery, storage, handling, and installation instructions. 	45 46
47 48 49	PART 2 - PRODUCTS	47 48 49
50 51	2.01 FABRICATION	50 51
52 53	A. The geocomposite drainage layer shall be formed by thermally bonding a nonwoven geotextile to both faces of a geonet. Heat boding shall	52 53

grades shown on the contract drawings.

53 /

The geocomponent drainage media shall be placed only on geomembrane that has been approved by the Geomembrane Installer and accepted by the CQC Consultant. The Contractor shall provide temporary anchorage of the geocomposite drainage media at the top of berms during installation to prevent movement during construction. Permanent bonding to the geomembrane is prohibited. Adjacent rolls of geonet shall be overlapped at a distance of at least 3 IN and secured using polyethylene ties placed every 5 FT. Any geocomposite drainage media that is torn, crushed, or punctured shall be repaired or replaced by the Contractor at no additional cost to the Owner. The repair shall consist of a patch of the same geocomposite drainage media placed over the damaged are and overlapped a minimum of 12 IN from any point of damage. The patch shall be attached to the geonet using polyethylene ties placed at least every 5 FT. All soils placed over the composite drainage manner shall be placed in such a manner as to ensure: The geocomposite drainage media and the underlying geomembranes are not damaged in anyway. Minimal slippage of the geocomposite drainage media on the underlying geomembrane occurs; and No excess tensile stresses occur in the geocomposite drainage media. **QUALITY CONTROL** 2.02 Prior to installation to the geocomposite drainage media, the CQC Consultant shall provide quality control certificates signed by the Manufacturer's quality assurance manager for every 50,000 ft2 of geocomposite drainage media to be installed. The Contractor shall submit to the CQC Consultant for approval two full sets of field erection drawings showing panel layout for the geocomposite drainage media. The erection drawings shall show panel lengths, locations, overlaps, method of securing joints, jointing to penetrations as shown on the contract drawings.

END OF SECTION

01	SECTION 03002	01 02
02 03	CONCRETE	03 04
04 05	PART 1 - GENERAL	05 06
06 07	1.01 SUMMARY	07 08
08 09 10 11 12 13	 A. Section Includes: 1. Cast-in-place concrete and grout. 2. Concrete mixes, proportioning, and source quality control for precast concrete. 	09 10 11 12 13
14 15 16 17 18 19	 B. Related Sections include but are not necessarily limited to: 1. Division 0 - Bidding Requirements, Contract Forms, and Conditions of the Contract. 2. Division 1 - General Requirements. 3. Section 03431 - Precast Concrete. 	14 15 16 17 18 19
20	1.02 QUALITY STANDARDS	20 21
21 22 23 24 25 26 27 28 29 31 32 33 33 33 33 34 44 45 47 47	A. Referenced Standards: 1. American Concrete Institute (ACI): a. SP-19, Cement and Concrete Terminology. b. 211.1, Standard Practice for Selecting Proportions for Normal and Heavyweight Concrete. c. 212.1R, Admixtures for Concrete. d. 212.2R, Guide for Use of Admixtures in Concrete. e. 214, Recommended Practice for Evaluation of Compression Test Results of Field Concrete. f. 304, Recommended Practice for Measuring, Mixing, Transporting, and Placing Concrete. g. 305R, Hot Weather Concreting. h. 306R, Cold Weather Concreting. i. 318, Building Code Requirements for Reinforced Concrete. j. 347, Recommended Practice for Concrete Formwork. 2. American Society for Testing and Materials (ASTM): a. A82, Standard Specifications for Cold Drawn Steel Wire for Concrete Reinforcement. b. A185, Standard Specification for Welded Steel Wire Fabric for Concrete Reinforcement. c. A615, Standard Specification for Deformed and Plain Billet Steel Bars for Concrete Reinforcement Including Supplementary Requirements S1. d. C31, Standard Method of Making and Curing Concrete Test Specimens in the Field. e. C33, Standard Specification for Concrete Aggregates.	22 22 23 24 25 26 27 28 29 31 33 33 34 35 36 37 38 39 41 42 43 44 45 47
48 49 50	f. C39, Standard Method of Test for Compressive Strength of Cylindrical Concrete Specimens.	48 49 50
51 52 53	h. C138, Standard Method of Test for Unit Weight, Yield, and Air Content (Gravimetric) of Concrete.	51 52 53

				01
01			Concrete.	02 /
02			j. C150, Standard Specification for Portland Cement.	
03			k. C157, Test Method for Length Change of Hardened Hydraulic	03 🖔
04			Cement Mortar and Concrete.	04
05			1. C171, Standard Specification for Sheet Materials for Curing	05
06			Concrete.	06
07			m. C172, Standard Method of Sampling Fresh Concrete.	07
08			n. C173, Standard Method of Test for Air Content of Freshly	80
09			Mixed Concrete by the Volumetric Method.	09
			and at 1 th 11 th CM 11 th Country Company Tout	10
10			o. C192, Standard Method of Making and Curing Concrete lest Specimens in the Laboratory.	11
11			Specimens in the Laboratory.	12
12			p. C231, Standard Method of Test for Air Content of Freshly	13
13		-	Mixed Concrete by the Pressure Method.	
14			q. C260, Standard Specification for Air Entraining Admixtures	14
15			for Concrete.	15
16			r. C289, Test Method for Potential Reactivity of Aggregates	16
17			(Chemical Method).	17
18			s. C309, Standard Specification for Liquid Membrane Forming	18
19			Compounds for Curing Concrete.	19
20			t. C494, Standard Specification for Chemical Admixtures for	20
21			Concrete.	21
22			v. C496, Standard Method of Test for Splitting Tensile	22
			Strength of Cylindrical Concrete Specimens.	23
23			and the contract of the contra	24
24			w. C595, Specification for Blended Hydraulic Lements.	25
25			x. C618, Standard Specification for Fly Ash and Raw or	
26			Calcined Natural Pozzolan for Use as a Mineral Admixture	26
27			in Portland Cement Concrete.	27
28			y. E329, Standard Recommended Practice for Inspection and	28 (
29			Testing Agencies for Concrete, Steel, and Bituminous	29
30			Materials as Used in Construction.	30
31		3.	Federal Specification (FS):	31
32			a. TT-S-227b, Sealer Compound; Rubber Base, Two Component.	32
33			b. LLL-B-810B, Building Board, (Hardboard) Hard Pressed,	33
34			Vegetable Fiber.	34
35		4.	Corps of Engineers: Specification CRD-C572 Polyvinyl	35
	•	4.		36
36			Waterstops.	37
37	_	Α.	1*1 0 . 41 .:	
38	В.		lity Control:	38
39		1.	Concrete testing agency.	39
40			a. Contractor to employ and pay for services of a testing	40
41			laboratory to:	41
42			 Perform materials evaluation. 	42
43			2) Design concrete mixes.	43
44			b. Concrete testing agency to meet requirements of ASTM	44
45			E329.	45
46		2.	Do not begin concrete production until proposed concrete mix	46
40 47		٠.	design has been approved by Engineer.	47
				48
48			a. Approval of concrete mix design by Engineer does not	49
49			relieve Contractor of his responsibility to provide	50
50		_	concrete that meets the requirements of this Specification.	
51		3.	Adjust concrete mix designs when material characteristics, job	51
52			conditions, weather, strength test results or other	52
53			circumstances warrant.	53

```
Do not use revised concrete mixes until submitted to and
                                                                                    01
01
                                                                                    02
02
                    approved by Engineer.
                                                                                    03
03
           Qualifications: Ready mixed concrete batch plant certified by
                                                                                    04
04
                                                                                    05
           National Ready Mixed Concrete Association (NRMCA).
05
                                                                                    06
06
                                                                                    07
    1.03 DEFINITIONS
07
                                                                                    08
08
                                                                                    09
           Per ACI SP-19 except as modified herein:
09
                                                                                    10
           1. Concrete fill: Non-structural concrete.
10
                Concrete Testing Agency: Testing agency employed to perform
                                                                                    11
11
                                                                                    12
12
                materials evaluation, design of concrete mixes or testing of
                                                                                    13
                concrete placed during construction.
13
                                                                                    14
                Exposed concrete: Exposed to view after construction is
14
                                                                                    15
15
                complete.
                                                                                    16
            4. Indicated: Indicated by Contract Documents.
16
                Lean concrete: Concrete with low cement content.
                                                                                    17
17
           5.
                Nonexposed concrete: Not exposed to view after construction
                                                                                    18
· 18
           6.
                                                                                    19
                is complete.
19
                                                                                    20
                Required: Required by Contract Documents.
20
           7.
                                                                                    21
                Specified strength: Specified compressive strength at 28
21
                                                                                    22
22
                davs.
                                                                                    23
                Submitted: Submitted to Engineer.
23
                                                                                    24
24
                                                                                    25
    1.04 SUBMITTALS
                                                                                    26
26
                                                                                    27
 27
           Shop Drawings:
                                                                                    28
                See Section 01300.
 28
            1.
                                                                                    29
                Concrete mix designs proposed for use. Concrete mix design
 29
                                                                                    30
                submittal to include the following information:
 30
                    Sieve analysis and source of fine and coarse aggregates.
                                                                                    31
 31
                                                                                    32
 32
                    Test for aggregate organic impurities.
                                                                                    33
                    Test for deleterious aggregate per ASTM C289.
 33
                С.
                    Proportioning of all materials.
                                                                                    34
 34
                d.
                                                                                    35
                    Type of cement with mill certificate for cement.
 35
                e.
                    Type of fly ash with certificate of conformance to
                                                                                    36
 36
                                                                                    37
 37
                    specification requirements.
                                                                                    38
                    Slump.
 38 ·
                g.
                    Air content.
                                                                                    39
 39
                h.
                                                                                    40
 40
                i.
                    Brand, type, ASTM designation, and quantity of each
                                                                                    41
                    admixture proposed for use.
 41
                    28-day cylinder compressive test results of trial mixes
                                                                                    42
 42
                    per ACI 318 and as indicated herein.
                                                                                    43
 43
                                                                                    44
                    Shrinkage test results.
 44
                    Standard deviation value for concrete production facility.
                                                                                    45
 45
                Manufacturer and type of joint filler, joint sealant, curing
                                                                                    46
 46
                                                                                    47
 47
                agent and chemical floor hardener.
                Manufacturer and type of bonding and patching mortar and
                                                                                    48
 48
                                                                                    49
 49
                bonding adhesive used at construction joints.
                                                                                    50
                Manufacturer and type of nonshrink grout and the cure/seal
 50
                compound required for the nonshrink grout.
                                                                                    51
 51
                                                                                    52
 52
                Reinforcing steel: Show grade, sizes, number, configuration,
                                                                                     53
 53
                spacing, location and all fabrication and placement details.
```

```
In sufficient detail to permit installation of reinforcing
                                                                                     01
01
                    without having to make reference to Contract Drawings.
                                                                                     02
02
                                                                                     03
                    Obtain approval of shop drawings by Engineer before
03
                                                                                     04
                    fabrication.
04
                                                                                     05
                    Mill certificates.
05
               С.
                                                                                     06
06
                                                                                     07
           DELIVERY, STORAGE, AND HANDLING
07
    1.05
                                                                                     08
08
                                                                                     09
           Delivery:
09
                                                                                     10
           1. Concrete:
10
                a. Prepare a delivery ticket for each load for ready-mixed
                                                                                     11
11
                                                                                     1.2
                 concrete.
12
                b. Truck operator shall hand ticket to Contractor at the time
                                                                                     13
13
                                                                                     14
                    of delivery. All tickets should be available for review
14
                                                                                     15
                    by Engineer.
15
                                                                                     16
                    Ticket to show:
16
                                                                                     17
                        Mix identification mark.
17
                                                                                     18
                        Ouantity delivered.
                    2)
18
                                                                                     19
                    3 i
                        Amount of each material in batch.
19
                                                                                     20
                        Outdoor temp in the shade.
                    4)
20
                                                                                     21
                        Time at which cement was added.
                    5)
21
                        Numerical sequence of the delivery.
                                                                                     22
22
                                                                                     23
                        Amount of water added.
23
                                                                                     24
                Reinforcing steel: Ship to jobsite with attached plastic
24
                                                                                     25
                or metal tags with permanent mark numbers.
25
                                                                                     26
                    Mark numbers to match shop drawing mark number.
26
                                                                                     27
27
                                                                                     28(
28
                                                                                     29
    PART 2 - PRODUCTS
29
                                                                                     30
30
                                                                                     31
     2.01 ACCEPTABLE MANUFACTURERS
31
                                                                                     32
32
                                                                                      33
            Subject to compliance with the Contract Documents, the following
 33
                                                                                      34
            manufacturers are acceptable:
 34
                                                                                      35
            1. Nonshrink, nonmetallic grout:
 35
                                                                                      36
                    Sika "SikaGrout 212."
 36
                                                                                      37
                    Gifford Hill "Supreme Grout."
 37
                                                                                      38
                    Master Builders "Masterflow 713."
 38
                                                                                      39
                    Or equal.
 39
                d.
                                                                                      40
                Expansion joint fillers:
 40
                                                                                      41
                a. Permaglaze Co.
 41
                                                                                      42
 42
                     Rubatex Corp.
                                                                                      43
                    Williams Products, Inc.
 43
                c.
                                                                                      44
                    Or equal.
 44
                d.
                                                                                      45
 45
            3. Form coating:
                     Richmond "Rich Cote."
                                                                                      46
 46
                                                                                      47
                     Industrial Lubricants "Nox-Crete Form Coating."
 47
                                                                                      48
                     Protex "Pro-Cote."
 48
                C.
                                                                                      49
                     Or equal.
 49
                                                                                      50
                Prefabricated forms:
 50
                                                                                      51
                     Simplex "Industrial Steel Frame Forms."
 51
                 a.
                     Symons "Steel Ply."
                                                                                      52
 52
                 Ь.
                                                                                      53
 53
                     Universal "Uniform."
```

01			d. Or equal.	01
02 03	2.02	MATE	RIALS	02 03
04 05	Α.	Por	tland Cement: Conform to ASTM C150 Type II	04 05 06
06 07	В.		Ash:	07 08
08 09 10		2.	ASTM C618, Class F. Nonstaining. a. Hardened concrete containing fly ash to be uniform light	09 10
11 12		3.	gray color. Maximum loss on ignition: 6 percent.	11 12
13 14	•		Compatible with other concrete ingredients. Obtain proposed fly ash from a source approved by the State	13 14
15 16		•	Highway Department in the state where the Project is located for use in concrete for bridges.	15 16
17 18		6.		17 18
19	C.	Adm	ixtures:	19
20	٠.	1.	Air entraining admixtures: ASTM C260.	20
21		2.	Water reducing, retarding, and accelerating admixtures:	21
22			a. ASTM C494 Type A through E.	22
23			b. Conform to provisions of ACI 212.1R and ACI 212.2R.	23
24			c. Do not use retarding or accelerating admixtures unless	24
25			specifically approved in writing by Engineer and at no	25 26
26			cost to Owner. d. Follow manufacturer's instructions.	27
27				28
28 29		3.	e. Use chloride free admixtures only. Maximum total water soluble chloride ion content contributed	29
30		٥.	from all ingredients of concrete including water, aggregates,	30
31			cementitious materials and admixtures by weight percent of	31
32			cement:	32
33			a. 0.06 prestressed concrete.	33
34			b. 0.10 all other concrete.	34
35		4.	Do not use calcium chloride.	35
36		5.	Pozzolanic admixtures: ASTM C618.	36
37		6.	Provide admixtures of same type, manufacturer and quantity as	37
38			used in establishing required concrete proportions in the mix	38
39			design.	39
40				40
41	D	. Wat	er: Potable, clean, free of oils, acids and organic matter.	41
42		_		42
43	E		regates:	43
44		1.	Normal weight concrete: ASTM C33, except as modified below.	44
45		2.	Fine aggregate: Clean natural sand.	45
46		_	a. No manufactured or artificial sand.	46
47		3.	Coarse aggregate: Crushed rock, natural gravel, or other	47
48			inert granular material.	48
49		A	a. Maximum amount of clay or shale particles: 1 percent.	49 50
50		4.	Gradation of coarse aggregate:	50 51
51			a. Lean concrete and concrete topping: Size #7.b. All other concrete: Size #57 or #67.	52
52		E	b. All other concrete: Size #5/ or #6/.Coarse aggregate for lightweight concrete: ASTM C330.	53
53	•	5.	codise aggregate for rightweight concrete. Astri cost.	J.3

```
01
                   Maximum size: 3/4 IN.
01
                                                                                    02
02
                                                                                    03
           Concrete Grout:
03
                                                                                    04
               Nonshrink nonmetallic grout:
04
                   Nonmetallic, noncorrosive, nonstaining, premixed with
                                                                                    05
05
                                                                                    06
                   only water to be added.
06
                   Grout to produce a positive but controlled expansion.
                                                                                    07
07
                                                                                    80
                   Mass expansion not to be created by gas liberation.
08
               С.
                                                                                    09
                   Minimum compressive strength of nonshrink grout at 28
09
                                                                                    10
                    days: 6500 psi.
10
                                                                                    11
11
                                                                                    12
12
       G.
           Reinforcing Steel:
                                                                                    13
               Reinforcing bars: ASTM A615, Grade 60.
13
                                                                                    14
                    Provide with epoxy coating per ASTM A775.
14
                                                                                    15
               Welded wire fabric: ASTM A185.
15
                                                                                    16
                    Minimum yield strength: 60,000 psi.
16
                                                                                    17
               Column spirals: ASTM A82.
17
                                                                                    18
· 18
                                                                                    19
           Forms:
19
       Н.
                                                                                    20
               Prefabricated or job built.
20
           1.
                Plywood: PS1, waterproof, resin bonded, exterior-type
                                                                                    21
21
                                                                                    22
                Douglas Fir.
22
                                                                                    23
                    Face adjacent to concrete Grade B or better.
23
                Fiberboard: Fed Spec LLL-B-810, Type IX, tempered, waterproof,
                                                                                    24
24
                                                                                    25
                screen back, concrete form hardboard.
25
                                                                                    26
                Lumber: Straight; uniform width and thickness; and free
26
                                                                                    27
                from knots, offsets, holes, dents, and other surface defects.
27
                Chamfer strips: Clear white pine, surface against concrete
                                                                                    28
28
                                                                                    29
                planed.
29
                                                                                    30
                Form ties: Removable end, permanently embedded body type
30
                with cones on outer ends not requiring auxiliary spreaders.
                                                                                    31
31
                                                                                    32
                a. Cone diameter: 3/4 IN minimum to 1 IN maximum.
32
                    Embedded portion 1 IN minimum back from concrete face.
                                                                                    33
 33
                                                                                    34
                    If not provided with threaded ends, constructed for
 34
                                                                                    35
                    breaking off ends without damage to concrete.
 35
                                                                                    36
                Form release: Nonstaining and shall not prevent bonding of
 36
                                                                                     37
                future finishes to concrete surface.
 37
                                                                                     38
                    Nontoxic 30 days after application.
38 ·
                                                                                     39
 39
                                                                                     40
            Chairs, Runners, Bolsters, Spacers, and Hangers:
 40
                Stainless steel, epoxy coated, or plastic coated metal.
                                                                                     41
 41
                                                                                     42
                    Plastic coated: Rebar support tips in contact with the
 42
                                                                                     43
 43
                    forms only.
                                                                                     44
 44
                                                                                     45
 45
        J.
            Expansion Joint Filler:
                                                                                     46
                1. Asphalt impregnated fiber type.
 46
                                                                                     47
 47
                                                                                     48
     2.03 CONCRETE MIXES
 48
                                                                                     49
 49
                                                                                     50
 50
            General:
        Α.
                All concrete to be ready mixed concrete conforming to ASTM
                                                                                     51
 51
                                                                                     52
 52
                Provide concrete of specified quality capable of being placed
                                                                                     53
 53
```

01 02 03 04		without segregation and, when cured, of developing all 01 properties required. 02 3. All concrete to be normal weight concrete. 03	
05 06 07	В.	Strength: 1. Provide specified strength and type of concrete for each use in structure(s) as follows: 05 06 07 08	
08 09 10		SPECIFIED 09 TYPE WEIGHT STRENGTH* 10 ==== 11	
11 12 13		Precast Concrete Normal weight 5000 psi 12 All other Concrete Normal weight 4000 psi 13	
14 15		*Minimum 28-day compressive strength. 15	
16 17 18	С.	Air Entrainment: Provide air entrainment in all concrete 17 resulting in a total air content percent by volume as follows: 18 19	,
19 20		MAX AGGREGATE SIZE TOTAL AIR CONTENT PERCENT 20	•
21 22		1 IN or 3/4 IN 5 to 7 22	
23 24		. 24	
25 26		1. Air content to be measured in accordance with ASTM C231, ASTM C173, or ASTM C138.	;
27 28 29 30 31 32 33 34	D.	Slump: 4 IN maximum, 1 IN minimum. 1. Measured at point of discharge of the concrete into the concrete construction member. 2. Pumped concrete: Provide concrete with appropriate mix design so that slump of concrete at discharge end of pump hose does not exceed maximum slump specified above. 3. Determine slump per ASTM C143.	}) } }
35 36 37 38 39 40 41 42 43	Ε.	Selection of Proportions: 1. General - Proportion ingredients to: a. Produce proper workability, durability, strength, and other required properties. b. Prevent segregation and collection of excessive free water on surface. 2. Minimum cement contents and maximum water cement ratios for concrete to be as follows: 43	5 7 3 9 1 2 3
44 45		MINIMUM CEMENT, LB/CY 45	5
46 47 48		SPECIFIED MAXIMUM AGGREGATE SIZE, IN CEMENT RATIO 47 STRENGTH 1/2 3/4 1 BY WEIGHT 48	7 3
49 50 51 52 53		3000 517 517 0.45 50 4000 611 611 611 0.45 51 5000 686 665 0.40 52	0 1 2

Extend reinforcement to within 2 IN of concrete perimeter

01 02 03 04 05 06 07 08 09 10 11 12 13 14 15 16 17 18 19 20		edges. a. If perimeter edge is earth formed, extend reinforcement to within 3 IN of the edge. Unless otherwise indicated, provide minimum concrete cover as follows: a. Concrete deposited against earth: 3 IN. b. Formed surfaces exposed to weather or in contact with earth: 2 IN for reinforcing bars #6 or larger; 1-1/2 IN for reinforcing bars less than #6. c. Formed surfaces exposed to or located above any liquid: 10 2 IN. d. Interior surfaces: 1-1/2 IN for beams, girders and columns; 3/4 IN or bar diameter, whichever is greater, for slabs, walls and joists. Do not weld reinforcing bars. Uelded wire fabric: a. Install welded wire fabric in maximum practical sizes. b. Splice sides and ends with a splice lap length measured between outermost cross wires of each fabric sheet not less than:
21 22 23 24 25 26		1) One spacing of cross wires plus 2 IN. 2) 1.5 x development length. 22 3) 6 IN. 23 c. Development length: ACI 318 basic development length for the specified fabric yield strength. 25 26
27 28 29 30 31 32 33 34 35 36	Ε.	Construction, Expansion, and Contraction Joints: 27 28 2. Provide at locations approved by the Engineer. 28 2. At least 48 HRS shall elapse between placing of adjoining concrete construction. 30 31 32 32 33 34 35 36
37 38 39 40 41 42 43	F.	Embedments: 1. Set and build in anchorage devices and other embedded items required for other work that is attached to, or supported by concrete. 2. Use setting diagrams, templates and instructions for locating and setting. 41 42 43
44 45 46 47 48	G.	Preparation: 44 1. Clean and adjust forms prior to concrete placement. 45 2. Tighten forms to prevent mortar leakage. 46 3. Coat form surfaces with form release agents prior to placing reinforcing bars in forms. 48
49 50 51 52 53	Н.	Placing Concrete: 1. Place concrete in compliance with ACI 304 and 304.2R. 2. Place in a continuous operation within planned joints or sections. 53

01 02		5.	Form materials left in place may be considered as curing materials for surfaces in contact with the form materials	01 02
03			except in periods of hot weather.	03
04		6.	In hot weather follow curing procedures outlined in ACI 305R.	04
05		7.	In cold weather follow curing procedures outlined in ACI 306R.	05
06		8.	If forms are removed before 7 days have elapsed, finish	06
07	•	٠.	curing of formed surfaces by one of above methods for the	07
08			remainder of the curing period.	08
09		9.	Curing vertical surfaces with a curing compound: Cover	09
		٦.	vertical surfaces with a minimum of two coats of the curing	10
10				11
11			compound.	
12			a. Allow the preceding coat to completely dry prior to	12
13		-	applying the next coat.	13
14			b. Apply the first coat of curing compound immediately after	14
15			form removal.	15
16			c. Vertical surface at the time of receiving the first coat	16
17			shall be damp with no free water on the surface.	17
18			d. A vertical surface is defined as any surface steeper than	18
19			1 vertical to 4 horizontal.	19
20				20
21	3.02	CONC	RETE FINISHES	21
22	0.02	00,,0		22
23	Δ	Tol	erances:	23
24	7.	1.		24
25		2.	Class B: 1/4 IN in 10 FT.	25
		۷.	C1855 B. 1/4 IN IN 10 11.	26
26	ь	Cina	force Expected to Views	27
27	В.		faces Exposed to View:	28
28		1.	Remove fins and projections, and patch voids, air pockets,	
29			and honeycomb areas with cement grout.	29
30	1.	2.	Fill tie holes with nonshrink nonmetallic grout.	30
31	av [*]	_		31
32	С.		faces Not Exposed to View:	32
33		1.	Patch voids, air pockets and honeycomb areas with cement	33
34			grout.	34
35		2.	Fill tie holes with nonshrink nonmetallic grout.	35
36			,	36
37	D.	Sla	b Float Finish:	37
38		1.	After concrete has been placed, consolidated, struck off,	38
39			and leveled, do no further work until ready for floating.	39
40		2.	Begin floating when water sheen has disappeared and surface	40
41			has stiffened sufficiently to permit operation.	41
42		3.	During or after first floating, check planeness of entire	42
43		J.	surface with a 10 FT straightedge applied at not less than	43
			two different angles.	44
44				45
45		4.	Cut down all high spots and fill all low spots during this	
46			procedure to produce a surface within Class B tolerance	46
47		_	throughout.	47
48		5.	Refloat slab immediately to a uniform sandy texture.	48
49				49
50	Ε.	Tro	weled Finish:	50
51		1.	Float finish surface.	51
52		2.	Next power trowel, and finally hand trowel.	52
53		3.		53

01			1) One at 7 days.	01
02			2) Two at 28 days.	02
03			3) One spare for 56 day break if requested by Engineer.	03
04		2	Strength test - frequency:	04
		۲.		05
05				06
06			b. Not less than one test for each 50 CY or major fraction	
07			thereof placed in one day.	07
80			 Not less than one test for each type of concrete poured. 	80
09			d. Not less than one test for each concrete structure	09
10			exceeding 2 CY volume.	10
11		3.	· · · · · · · · · · · · · · · · · · ·	11
12		•	a. Determined for each strength test sample.	12.
13			b. Additional slump tests may be taken.	13
14	•	4.	Air content: Per ASTM C231, C173, and C138.	14
		4.		15
15		-	a. Determined for each strength test sample.	16
16		5.	Temperature: Determined for each strength test sample.	
17		6.	Unit weight of lightweight concrete.	17
18			a. Determined for each strength test sample.	18
19			b. Sample taken at point of discharge of fresh concrete.	19
20				20
21	С.	Eva	luation of Tests:	21
22		1.	Strength test results: Average of 28-day strength of two	22
23			cylinders from each sample.	23
24			a. If one cylinder manifests evidence of improper sampling,	24
25			molding, handling, curing or testings, strength of	25
26			remaining cylinder will be test result.	26
				27
27				28
28			discarded.	
29	_	_		29
30		Acc	eptance of Concrete:	30
31		1.	Strength level of each type of concrete shall be considered	31
32			satisfactory if both of the following requirements are met:	32
33	•		 a. Average of all sets of three consecutive strength tests 	33
34			equals or exceeds the required specified 28-day	34
35			compressive strength.	35
36			b. No individual strength test falls below the required	36
37			specified 28-day compressive strength by more than 500 psi.	37
38			specified to day compressive outsings and a small error period	38
39	3.05	SCHE	EDULES	39
40	J.0J	JUIL	.DULL3	40
	٨	Гои	Types.	41
41	Α.		rm Types:	
42		1.		42
43			a. Prefabricated plywood panel forms, job-built plywood forms,	43
44			or forms lined with plywood or fiberboard.	44
45			b. Laid out in a regular and uniform pattern with long	45
46			dimensions vertical and joints aligned.	46
47			c. Produce finished surfaces free from offsets, ridges, waves,	47
48			and concave or convex areas.	48
49			d. Construct forms sufficiently tight to prevent leakage of	49
50			mortar.	50
51		2.	Surfaces normally submerged or not normally exposed to view:	51
52		٠.	a. Wood or steel forms sufficiently tight to prevent leakage	52
53			of mortar.	53
55			or morear.	55

01		3. Other types of forms may be used:	01
02		 a. For surfaces not restricted to plywood or lined forms. 	02
03		b. As backing for form lining.	03
04			04
05	В.	Grout:	05
06		 Nonshrinking nonmetallic grout: General use. 	06
07			07
08	С.	Concrete:	80
09		 Precast concrete: Where indicated on Drawings. 	09
10		2. Normal weight concrete: All other locations.	10
11			11
	D.	Concrete Finishes:	12
12 13		 Grout cleaned finish: Where indicated on Drawings. 	13
14		2. Slab finishes:	14
15		a. Use following finishes as applicable, unless otherwise	15 16
16		indicated:	
17		 Troweled finish: Base slabs of structures, and 	17
18		equipment bases.	18
19		Broom finish: Sidewalks, docks, concrete stairs,	19
20		and ramps.	20
21			21
22			22
23		END OF SECTION	23

01		01
02 03 04	PRECAST CONCRETE	02 03 04
05 06	PART 1 - GENERAL	05 06 07
07 08	1.01 SUMMARY	07 08 09
09 10 11 12	A. Section Includes: 1. Precast concrete structures.	10 11 12
13 14 15	B. Related Sections include: 1. Section 03002 - Concrete.	13 14 15
16 17	1.02 QUALITY STANDARDS	16 17
18 19 20 21 22 22 24 25 26 27 28 29 30 31 32 33 34 44 44 44 44 44 44 44 44 44 44 44	 American Association of State Highway and Transportation Officials (AASHTO): a. Standard Specifications for Highway Bridges. American Concrete Institute (ACI): 	18922222222223333333333444444444444444444
49 50 51 52 53	 b. PCI Design Handbook Precast and Prestressed Concrete. B. Qualifications: 1. Provide units manufactured by plant which has regularly and continuously engaged in manufacture of units of same type as 	49 50 51 52 53

0.1		there were ined for a minimum of 3 years	01
01 02		those required for a minimum of 3 years. 2. Assure manufacturer's testing facilities meet requirements	02
03		of ASTM E329.	03
04		 Welding operators and processes to be qualified in 	04 05
05		accordance with: a. AWS DI.1 for welding steel shapes and plates.	06
06 07		a. AWS D1.1 for welding steel shapes and plates.b. AWS D1.4 for welding reinforcing bars.	07
08		4. Welding operators to have passed qualification tests for type	80
09		of welding required during the previous 12 months prior to	09
10	_	commencement of welding.	10 11
11 12	1.03	DEFINITIONS	12
13	1.03		13
14	Α.	Installer or Applicator: Installer or applicator is the person	14 15
15		actually installing or applying the product in the field at the	16
16 17		Project site.	17
18	1.04	SUBMITTALS	18
19			19 20
20	Α.	Shop Drawings: 1. See Section 01300.	21
21 22		1. See Section 01300. 2. Product technical data including:	22
23		 a. Acknowledgement that products submitted meet requirements 	23
24		of standards referenced.	24
25		 b. Manufacturer's installation instructions. c. Sizes, types and manufacturer of neoprene bearing pads. 	25 26
26 27		 c. Sizes, types and manufacturer of neoprene bearing pags. d. Hardware to be utilized to support suspended appurtenances. 	27
28		3. Shop drawings and erection plans for precast units, their	28
29		connections and supports showing:	29
30		a. Member size and location.	30 31
31		 b. Size, configuration, location and quantity of reinforcing bars. 	32
32 33	•	c. Size and location of openings verified by Contractor.	33
34		d. Size, number, and locations of embedded metal items and	34
35		connections.	35
36		e. Required concrete strengths. f. Identification of each unit using same standard marking	36 37
37 38		f. Identification of each unit using same standard marking numbers as used to mark actual units.	38
39		 Concrete mix design(s) including submittal information 	39
40		defined in Sections 03002.	40
41		Coming of source quality control toots	41 42
42 43		Copies of source quality control tests.	43
44		6. Certification of manufacturer's testing facility	44
45		qualifications.	45
46		THE THERE AND LIANDITAN	46
47	1.05	DELIVERY, STORAGE, AND HANDLING	47 48
48 49	Α.	Transport and handle units with appropriate equipment to protect	49
50	71.	from dirt, chipping and damage.	50
51			51
52	В.	Do not place units in positions which will cause overstress, warp	52 53

```
01
01
                                                                                    02
02
       C. Utilize lifting inserts.
                                                                                    03
03
                                                                                    04
       D. Store off ground.
04
                                                                                    05
05
           Place stored units so that identification marks are visible.
                                                                                    06
06
                                                                                    07
07
           Separate stacked members by wood battens across full width of
                                                                                    08
80
                                                                                    09
09
           each bearing point.
                                                                                    10
10
           Stack so that lifting devices are accessible and undamaged.
                                                                                    11
11
                                                                                    12
12
                                                                                    13
       H. Do not use upper member of stacked tier as storage area.
13
                                                                                    14
14
                                                                                    15
15
                                                                                    16
    PART 2 - PRODUCTS
16
                                                                                    17
17
                                                                                    18
    2.01 MATERIALS
18
                                                                                    19
19
                                                                                    20
20
           Concrete:
                                                                                    21
21
           1. Minimum 28-day compressive strength of 5000 psi.
                                                                                    22
                Provide concrete materials and proportions as required in
22
                                                                                    23
                Section 03002.
23
                                                                                    24
               Concrete color to be gray.
24
                                                                                    25
               Cement: Conform to ASTM C150 Type I or III.
25
                                                                                    26
26
                                                                                    27
27
       B. Aggregates:
                                                                                    28
           1.
               Crushed rock indigenous to area.
28
                                                                                    29
29
               ASTM C33, Table 2, size number 67.
                                                                                    30
               Aggregate quality per Section 03002.
30
                                                                                    31
31
                                                                                    32
32
           Water:
                                                                                    33
           1. Potable, clean.
33
                                                                                    34
               Free of oils, acids, and organic matter.
34
                                                                                    35
35
                                                                                    36
           Maximum total chloride ion content contributed from all
36
                                                                                    37
37
            ingredients of concrete including water, aggregates, cement and
            admixtures measured as a weight percent of cement to not exceed
                                                                                    38
38
            0.06 for prestressed concrete and 0.10 for all other precast
                                                                                    39
39
                                                                                    40
40
            concrete.
                                                                                     41
41
                                                                                     42
42
           Reinforcing Steel and Welded Wire Fabric: See Section 03002.
       Ε.
                                                                                     43
43
                                                                                     44
44
        F.
            Electrodes:
            1. E70 series conforming to AWS A5.1 or A5.5 for welding steel
                                                                                     45
45
                                                                                     46
46
                shapes and plates.
                                                                                     47
            2. E90 series conforming to AWS A5.5 for welding rebar.
47
                                                                                     48
48
                                                                                     49
           Metal Anchors, Inserts and Anchorages: Galvanized.
49
                                                                                     50
50
                                                                                     51
    2.02
51
            ACCESSORIES
                                                                                     52
52
            Provide all connection items, lifting devices, anchors, and other
                                                                                     53
53
```

welding strips into members at time of manufacture.

53,

28-day required compressive strengths.

01 02	3.02	ERECTION, INSTALLATION, APPLICATION	01 02 03 (
03 04 05 06	Α.	Contractor is responsible for all dewatering measures required for base soil preparation and for the correct bearing conditions needed for each precast structure.	04 05 06 07
07 08 09	В.	Give consideration to possible lack of stability or capacity of partially completed frame or structure.	08 09 10
10 11 12 13 14	C.	Contractor to be responsible for guying, shoring, and bracing of frame, walls and individual members as necessary to resist forces due to wind, erection, or any other source that may occur before a structure is completed.	11 12 13 14 15
15 16 17 18 19	D.	Use only erection equipment adequate for placing units at lines and elevations indicated on Drawings. Do not damage units or existing construction during erection. Erect units using lifting handles or inserts cast into the units.	16 17 18 19 20
20 21 22 23	Ε.	Weld steel shapes and plates per AWS D1.1 and reinforcing steel per AWS D1.4.	21 22 23
24 25	F.	Patch defective concrete surfaces in accordance with method approved by Engineer.	24 25 26
26 27	3.03	FIELD QUALITY CONTROL	27 28
28 29 30 31 32 33 34 35 36 37 38 39 40	Α.	Causes for rejection of units include, but are not necessarily limited to the following: 1. Cracked units. 2. Chipped, broken, or spalled edges. 3. Units not within allowable casting tolerances. 4. Voids or air pockets which, in opinion of Engineer, are too numerous or too large. 5. Non-uniform finish or appearance. 6. Low concrete strength. 7. Improperly placed embedded items and/or openings. 8. Exposed wire mesh or reinforcing.	29 30 31 32 33 34 35 36 37 38 39
41 42 43	В.	Do not stack sections concrete-to-concrete, but use wood separator strips or pads to prevent damage.	41 42 43
44 45 46 47 48 49	С.	On initial delivery of all precast units, the Contractor shall inspect each, and accept or reject each, and shall call upon the Engineer for opinion if he deems it necessary to do so. A written record of acceptance or rejection of delivered precast parts shall always be entered into the daily construction log.	44 45 46 47 48 49
50 51 52 53	D.	Replace any unit which exhibits damage to surfaces, finish, corners or edges which will be exposed to view after setting in place, or which is broken or cracked due to shrinkage, temperature, transportation, handling or erection, except, that when approved	50 51 52 53

01		in writing by Engineer unit may be repaired in place. Perform	01
02		such work at no additional expense to Owner.	02
03		Such Horiz de la management experience and an arrangement and arrangement arrangement and arrangement arrangem	03
04	F	Acceptance of repaired unit, repaired pursuant to written	04
05	<u>.</u> .	approval, is contingent upon repairs being skillfully done so as	05
06		to be sound, permanent, flush with adjacent surfaces and of color	06
07		and texture matching similar adjoining surfaces and showing no	07
08		apparent line of demarcation between original and repaired work.	30
09		Remove and replace other work damaged by removal of defective	09
10		panel members at no additional cost to Owner.	10
$\overline{11}$			13
12	3.04	CLEANING	. 12
13	0.0.		13
14	Α.	Leave units clean, free of traces of cleaning compound.	14
15	,,,		1!
16			16
17		END OF SECTION	17
18		4	18

.

01			01				
02			02				
03 04							
05 06	PART 1 - GENERAL						
07							
08 09	1.01 I		08 09				
10	Α.		10				
11			11				
12.		in the state of th	12 13				
13 14			14				
15		3. Although such work is not specifically indicated, furnish	15				
16		and install all supplementary or miscellaneous items,	16				
17		appar commisses and services increases and a	17 18				
18 19			19				
20	В.		20				
21	٥.	necessarily limited to the following piping systems:	21				
22		2. Louis de la company de la c	22				
23		2,020,	23 24				
24 25			25				
26			26				
27	1.02		27				
28	_		28				
29	Α.		29 30				
30 31			31				
32		3. Section 03431: Precast Concrete	32				
33			33				
34	ь	· ·	34 35				
35 36	В.		36				
37	1.03	SUBMITTALS	37				
38	•		38				
39	Α.	See Section 01300.	39				
40	В.	Verify on shop drawings dimensions, schedule of pipe, fittings,	40 41				
41 42	р.	hangers, supports and miscellaneous appurtenances. When special	42				
43		fittings are necessary, verify locations of items and include	43				
44		complete details.	44				
45		As well suspenses and again when work is complete, submit MAS	45 46				
46 47	С.	As work progresses and again when work is complete, submit "As- Recorded" drawings of piping systems including project items and	47				
47		pre-existing items. Identify complete location, elevation,	48				
49		description of piping systems. Relate piping systems to	49				
50		identified structures and appurtenances.	50				
51	n	Submit written verification of required quality control testing.	51 52				
52 53	D.	Submitt withten verification of required quality control testing.	53				

· 18

38 -

PART 2 - PRODUCTS

2.01 GENERAL PIPING SCHEDULE

A. Unless otherwise shown on drawings, piping system materials, fittings and appurtenances are subject to requirements of specific technical specifications and shall be as follows:

Service Category	Size Range	Piping System
Leachate Collection	all sizes	HDPE '
Leachate Gravity Header Piping	all sizes	HDPE
Culverts	all sizes	RCP or CMP

PART 3 - EXECUTION

3.01 DELIVERY, INSPECTION AND STORAGE

- A. Inspect materials thoroughly upon arrival. Remove damaged or rejected materials from site.
- B. Observe manufacturer's directions for delivery and storage of materials and accessories.
- C. Store materials on site in enclosures or under protective coverings above ground to keep clean and dry.

3.02 HANDLING OF PIPE

- A. Protect pipe coating during handling using methods recommended by manufacturer. Use of bare cables, chains, hooks, metal bars or narrow skids in contact with coated pipe is not permitted.
- B. Prevent damage to pipe during transit. Repair abrasions, scars, and blemishes. If repair of satisfactory quality cannot be achieved, replace damaged material immediately.
- C. Install piping to accurate lines and grades and support as required on drawings or described in specifications. When temporary supports are used, insure that sufficient rigidity is provided to prevent shifting or distortion of pipe. Install expansion devises as necessary to allow expansion and contraction movements.

3.03 PIPING - GENERAL

A. Minimum bury. Unless otherwise shown on the drawings, provide a

01 02 03 04		systems and appurtenances conveying water, fluids, or solutions subject to freezing.	02 03 04
05 06	3.04	PIPING WITHIN BUILDINGS, STRUCTURES AND UNITS	05 06
07 08 09	Α.	Install piping in vertical and horizontal alignment as shown on drawings.	07 08 09
10 11	В.	Use methods of piping support as shown on drawings.	10 11
12 13 14	С.	Locate and size sleeves required for piping system. Arrange insert or anchors at proper elevation and location.	12 13 14
15 16	3.05	PIPING OUTSIDE STRUCTURES	15 16
17 18 19	Α.	Install piping as shown on drawings with ample clearance and allowance for expansion or contraction.	17 18 19
20 21 22 23 24		Install flexible joint within two (2) FT of point where pipe enters or leaves structure. Install second flexible joint not more than six (6) FT nor less than four (4) FT from first joint. Provide balance of piping with standard laying lengths and in accordance with drawings.	20 21 22 23 24
25 26 27		PIPE INTERSECTIONS WITH STRUCTURES AND UNITS	25 26 27
28 29	Α.	Enter and exit through structure walls by using wall seals specified or as shown on drawings.	28 29 30
30 31 32	3.07	EQUIPMENT PIPE CONNECTIONS	3]
33 34 35 36 37 38 39 40	Α.	Exercise care in bolting flanged joints so that there is no restraint on the opposite end of pipe or fitting which would prevent uniform gasket pressure at connection or would cause unnecessary stresses to be transmitted to equipment flanges. Where push-on joints are used in conjunction with flanged joints, final positioning of push-on joints shall not be made until flange joints have been tightened without strain.	32 32 34 35 36 37 38
41 42 43 44	В.	Tighten flange bolts at uniform rate which will result in uniform gasket compression over entire area of joint. Provide tightening torque in accordance with manufacturer's recommendations.	4: 4: 4: 4:
45 46 47	С.	Support and match flange faces to uniform contact over their entire face area prior to installation of any bolt between the piping flange and equipment connecting flange.	4: 4: 4: 4:
48 49 50 51 52	D.	Permit piping connecting to equipment to freely move in directions parallel to longitudinal centerline when and while bolts in connection flange are tightened. Align, level, and wedge equipment into place during fitting and alignment of connecting piping. Grout equipment into place prior to final	50 50 50 50 50

B. Clean each pipe length thoroughly and inspect for compliance to

At completion of work and prior to final acceptance,

may have entered the system.

thoroughly clean work installed under these specifications. Clean equipment, fixtures, pipe, valves, and fittings of grease, metal cuttings, and sludge which may have accumulated by operation of system, from testing or from other causes. 3.14 TESTING AND INSPECTION Perform testing and inspection prior to cleaning and final acceptance. Acknowledge satisfactory performance of tests and inspections in writing to the Project Manager or CQA Consultant prior to final acceptance. 12. Types of testing and inspection to be employed for the piping systems include: Hydrostatic pressure testing. Low pressure air test. Test and inspect all pipes and joints in designated sections. Provide all necessary equipment and perform all work required in connection with the tests and inspections. The Contractor shall bear the cost of all testing and inspecting, locating and remedying of leaks and any necessary retesting and re-examination. E. Hydrostatic pressure testing. Provide temporary restraints for expansion joints for additional pressure load under test. Equipment in piping system with rated pressure lower than pipe test pressure, shall be isolated by valves or blind flanges. Test piping to hydrostatic test pressure scheduled on drawings or otherwise indicated in the CQA/CQC Plan. Low pressure test. F. 1. For gravity piping where low pressure testing is required or noted on schedules, comply with Testing Methods outlined in these paragraph specifications for test performance unless otherwise specified in the CQA/CQC Plan. Insure all gravity sewers comply with Infiltration - Exfiltration Testing criteria after backfill and compaction are satisfied. Infiltration. Perform and observe following testing criteria and procedures. Maximum infiltration allowance is 100 gpd/IN diameter/mile. Infiltration test procedure: Plug upper section of line. 1) Install suitable measuring device at lower end. 2) Measure amount of water flowing through outlet over a specified period of time. 3. Exfiltration. Perform and observe following testing criteria and procedures. Maximum exfiltration allowance is 100 gpd/IN diameter/mile. Exfiltration air test procedure:

Check pneumatic plugs for proper sealing.

/

01 02 03 04 05 06 07 08 09 10 11 12		 Place plugs in line at each manhole and inflate to 25 psig. Introduce low pressure air into sealed line until air pressure reaches 4 psig greater than average back pressure of any ground water that may be over the pipe. Use test gage conforming to ANSI B40.1 with 0 to 15 psi scale and an accuracy of 1 percent of full range. Allow two (2) minutes for air pressure to stabilize. After stabilization period (3.5 psig minimum pressure in pipe) discontinue air supply to line segment. Acceptable time for loss of one (1) psig of air pressure shall be: 	01 02 03 04 05 06 07 08 09 10 11 12 13			
15 16		Pipe Size (IN) Time, Minutes/100 FT	15 16			
17 18 19 20 21		6 0.7 8 1.2 10 1.5 12 1.8	17 18 19 20 21			
22 23 24 25 26 27	G.	materials, and related work and repeat pressure testing until 24 piping in each system meets the test criteria. Additional costs 25 to be paid by the Contractor. Caulking of screwed joints or 26 holes will not be acceptable. 27				
28 29 30 31 32 33 34 35 36 37 38 39	3.15	LOCATION OF BURIED OBSTACLES	28 29			
	Α.	Furnish exact location of buried utilities encountered and any below grade structures. Reference items to definitive reference point locations such as found property corners, existing structure lines and related fixed structures. Include such information as location, elevation, coverage, supports and additional pertinent information which will be required by future contractors for replacement servicing, or adjacent construction around any buried facility.	30 31 32 33 34 35 36 37 38			
40 41	В.	Incorporate information to "As-Recorded" drawings.	40 41			
42	3.15	SPECIAL REQUIREMENTS AND PIPING SPECIALTIES	42 43			
43 44 45 46 47 48 49 50 51 52 53	Α.	 Heat tracing. Provide electric heat tracing on pipe systems for freeze protection to locations shown on the drawings. Ensure heat tape is self-limiting, parallel circuit construction consisting of an inner core of conductive material between parallel copper bus wires, with inverse temperature-conductivity characteristics. Provide heat tracing as manufactured by Chemelex or equal. Provide all necessary components such as end seals, straps, tape and fitting brackets. 	44 45 46 47 48 49 50 51 52			

01	3.	Provide components and installations approved for Class I,	01
02	٠.	Division I explosion proof service (as applicable).	02 /
03	Δ	Install each system in strict accordance with manufacturer's	03 5
04	, .	instructions and recommendations.	04
05	5	Provide and connect thermostats.	05
06	٥.	1104 ldc alla connect onermostator	06
07			07
		END OF SECTION	08
08		END OF SECTION	

```
01
                                    SECTION 15064
01
                                                                                     02
02
                                                                                     03
                                    PIPE: PLASTIC
03
                                                                                     04
04
                                                                                     05
05
                                                                                     06
06
                                                                                     07
    PART 1 - GENERAL
07
                                                                                     80
08
                                                                                     09
           DESCRIPTION
09
    1.01
                                                                                     10
10
                                                                                     1.1
      · A.
11
           General:
                                                                                      12.
12
               Work items in project include, but are not necessarily limited
                                                                                     13
13
                                                                                      14
                to the following:
14
                                                                                      15
                a. HDPE Leachate Collection and Header Piping.
15
                                                                                      16
                b. HDPE Gravity Header Piping.
16
                                                                                      17
                   HDPE Force Main Piping.
17
                                                                                      18
                d. HDPE Cleanout Risers.
18
                                                                                      19
                Furnish all labor, materials, tools, equipment, and perform
19
                                                                                      20
                all work and services necessary for or incidental to the
20
                furnishing and installation, complete, of plastic pipe, as
                                                                                      21
21
                shown on drawings and specified in accordance with provisions
                                                                                      22
22
                of the Contract Documents.
                                                                                      23
23
                                                                                      24
                Completely coordinate work with that of all other trades.
24
                                                                                      25
                Although such work is not specifically shown or specified,
25
                all supplementary or miscellaneous items, appurtenances, and
                                                                                      26
26
                                                                                      27
                devices incidental to or necessary for a sound, secure,
27
                complete, and compatible installation shall be furnished and
                                                                                      28
28
                                                                                      29
29
                installed as part of this work.
                                                                                      30
30
                                                                                      31
31
    1.02
            OUALITY STANDARDS
                                                                                      32
32
                                                                                      33
            Refer to the following standards and include as part of these
33
                                                                                      34
            specifications:
34
                                                                                      35
35
                                                                                      36
36
            1. PVC Materials:
                                                                                      37
37
                                                                                      38
                ASTM D1785
                               Schedule 40, 80 and 120 PVC Plastic Pipe
38
                                                                                      39
                               External Loading Properties of Plastic Pipe
                ASTM D2412
39
                               by Parallel - Plate Loading
                                                                                      40
40
                               Solvent Cements for (PVC) Plastic Pipe, Tubing
                                                                                      41
41
                ASTM D2564
                                                                                      42
                               and Fittings
42
                                                                                      43
43
                ASTM D2729
                               (PVC) Sewer Pipe and Fittings
                               Type PSM - PVC Sewer Pipe and Fittings
                                                                                      44
44
                ASTM D3034
                                                                                      45
45
                ASTM D3212
                               Joints
                                                                                      46
46
                (HD) Polyethylene Materials:
                                                                                      47
47
                                                                                      48
                    D-1505, Density
48
                1)
                2) D-1238, Melt Index
                                                                                      49
49
                3) D-790, Flexural Modulus4) D-638, Tensile Strength
                                                                                      50
50
                                                                                      51
51
                                                                                      52
52
                5) D-1693, Environmental Stress Crack
                                                                                      53
                   D-2513, D-3261, D-2683, Molded Fittings
53
```

01 02 03		bedding in accordance with Drawings and Specification Section 02221.	01 02 03
04 05	3.04	CLEANING	04 05
06 07 08 09 10 11 12 13 14 15 16 17 18 19 20 21	Α.	 General Cleaning: Clean interior of piping systems thoroughly of foreign matter before installing. Maintain pipe in clean condition during installation. Before jointing pipe, thoroughly clean and wipe joint contact surfaces and then properly dress and make joint. Immediately prior to pressure testing of PVC piping systems, clean and remove grease, dirt or other foreign materials which may have entered the system. Upon completion of work and prior to final acceptance, thoroughly clean work installed under these specifications. Clean pipe, valves and fittings of debris which may have accumulated by operation of system, from testing or from other causes. 	06 07 08 09 10 11 - 12 13 14 15 16 17 18 19 20
	3.05	TESTING AND INSPECTION	21 22
22 23 24 25 26 27	Α.	Perform testing and inspection prior to cleaning and final acceptance. Acknowledge satisfactory performance of tests and inspections in writing to CQA Consultant prior to final acceptance.	23 24 25 26 27
28 29 30 31 32 33 34 35 36 37 38 39 40 41 42	В.	Types of testing and inspection to be employed for the piping systems include: Low Pressure Air Test unless otherwise approved by the Project Manager and CQA Consultant.	28 29 30 31
	, C.	Test and inspect all pipes, fittings and joints. Provide all necessary equipment and perform all work required in connection with the tests and inspections.	32 33 34 35
	D.	Bear the cost of all testing and inspecting, locating and remedying of Leaks, and any necessary retesting and re-examination.	36 37 38 39
	Ε.	Refer to Section 15060, Paragraph 3.13-F for low pressure test requirements.	40 41 42 43
43 44 45		END OF SECTION	44 45

01		SECTION 15066	01 02
02 03 04		PIPE: STAINLESS STEEL	03 04
05 06 07	PART 1	- GENERAL	05 06 07
07 08 09	1.01	SUMMARY	08 09
10 11 12	A.	General work included in this Section: 1. Stainless steel piping, fittings and appurtenances, as required to protect the cleanout riser piping.	10 11 12 13
13 14 15 16 17 18	В.	Related Sections include but are not necessarily limited to: 1. Division O - Bidding Requirements, Contract Forms, and Conditions of the Contract. 2. Division 1 - General Requirements. 3. Section 15060 - Pipe and Pipe Fittings: General.	14 15 16 17 18
19 20 21	1.02	QUALITY STANDARDS	19 20 21
22 23 24 25 26 27 28 29 30 31 32 33 33 33 33 33 34 44 44	Α.	 Referenced Standards: American National Standards Institute (ANSI): a. B16.5, Pipe Flanges and Flanged Fittings. American Society for Testing and Materials (ASTM): 	22 23 24 25 26 27 28 29 30 31 32 33 34 35 40 41 42 43
45 46	1.03	SUBMITTALS	45 46 47
47 48 49	Α.	Shop Drawings consistent with Section 01300.	48 49
50 51	PART	2 - PRODUCTS	50 51
52 53	2.01	MATERIALS	52 53

```
01
01
                                                                                     02
           Tubing: ASTM A269.
02
       Α.
                                                                                     03
           1. Filler material: Extra low carbon (ELC) with 0.03 percent
03
                                                                                     04
               maximum carbon.
04
                                                                                     05
05
                                                                                     06
       Β.
           Pipe:
06
                                                                                     07
           1. ASTM A778.
07
                                                                                     80
           2. ASTM A351.
08
                                                                                     09
09
                                                                                     10
           Pipe Fittings:
10
                                                                                     11
            1. ASTM A774.
11
                                                                                     12
12
            2.
               ASTM A351
                                                                                     13
13
                                                                                     14
           Nuts, Bolts and Washers:
14
                                                                                     15
            1. ASTM A320, Type 316.
15
                Two nuts provided for 1 IN DIA bolt applications and larger.
                                                                                     16
16
                                                                                     17
17
                                                                                     18
            Gasket Material:
· 18
                                                                                     19
            1. Rubber or neoprene.
19
                                                                                     20
                Temperature rating of 250 DegF.
20
                                                                                     21
21
                                                                                     22
22
    2.02 FABRICATION
                                                                                     23
23
                                                                                     24
           All tube, piping, fitting product to be immersion pickled
24
                                                                                     25
            subsequent to manufacturing and fabrication operations and prior
25
                                                                                     26
            to shipping.
26
                Pickling solution of 6-10 percent nitric acid and 3-4 percent
                                                                                     27
 27
                                                                                     28
                hydrofluoric acid.
 28
                                                                                     29
                Temperature and exact concentrations to be such only a modest
 29
                etch is produced but all oxidation and ferrous contamination
                                                                                     30
 30
                                                                                     31
                is removed from metal surface.
 31
                All pickling solution residues are to be neutralized after
                                                                                     32
 32
                                                                                     33
                pickling.
 33
                                                                                     34
 34
                                                                                     35
            Diameter tolerance and wall thickness tolerance are to conform
 35
                                                                                      36
            to ASTM A530.
 36
                                                                                     37
 37
                                                                                      38
            Joints.
 38 -
        С.
                                                                                     39
            1. Shop welded circumferential buttweld joints.
 39
                                                                                      40
                Van Stone joints using angle face rings with backing flanges.
 40
                                                                                      41
                ANSI B16.1, Class 150
 41
                                                                                      42
 42
                                                                                      43
 43
                                                                                      44
     PART 3 - EXECUTION
 44
                                                                                      45
 45
                                                                                      46
     3.01 EXAMINATION
 46
                                                                                      47
 47
             Prior to installation, inspect and verify condition of piping and
                                                                                      48
 48
             appurtenances. Installation constitutes installer's acceptance of
                                                                                      49
 49
                                                                                      50
             condition for satisfactory installation.
 50
                                                                                      51
 51
                                                                                      52
     3.02 PREPARATION
 52
                                                                                      53,
 53
```

01 02	Α.	Correct defects or conditions which may interfere with or prevent a satisfactory installation.	01 02
03 04 05	В.		03 04 05 06
06 07 08	3.03	INSTALLATION	07 08
09 10	Α.	Install stainless steel pipe as protective casing for 6" (Nom.) Dia. HDPE cleanout riser, as shown on the drawings.	09 10 11
11 12 13	В.	Embed the steel pipe within the concrete collar as shown on the drawings.	12 13 14
14 15 16	С.	Provide tamper resistant locking cap pipe end, as shown on the drawings.	15 16 17
17 18 19	3.04	FIELD QUALITY CONTROL	18
20 21	Α.	Test piping systems in accordance with Section 15060.	19 20 21
22	3.05	CLEANING	21 22 23 24
24 25	Α.	Clean in accordance with Section 15060.	25
26 27		END OF SECTION	26 27

```
01
                                  SECTION 15069
01
                                                                                    02
02
                                                                                    03
                                  REINFORCED CONCRETE
03
                                                                                    04
04
                                                                                    05
05
                                                                                    06
    PART 1 - GENERAL
06
                                                                                    07
07
                                                                                     08
08
    1.01 SUMMARY
                                                                                     09
09
            Work covered by this section includes supplying and installing RCP
                                                                                     10
10
                                                                                     11
            culverts and drop inlet RCPs as shown on the Plans.
11
                                                                                     12
12
                                                                                     13
            Related Sections include but are not necessarily limited to:
13
                                                                                     14
            1. Division O - Bidding Requirements, Contract Forms, and
14
                                                                                     15
                Conditions of the Contract.
15
                Division 1 - General Requirements.
                                                                                     16
 16
                Section 02221 - Trenching, Backfilling, and Compacting.
                                                                                     17
17
                                                                                     18
                Section 03002 - Concrete.
. 18
                                                                                     19
                Section 03431 - Precast Concrete.
 19
                                                                                     20
                Section 15060 - Pipe and Pipe Fittings: General.
 20
                                                                                     21
 21
                                                                                     22
     1.02 QUALITY STANDARDS
 22
                                                                                     23
 23
                                                                                     24
        A. Referenced Standards:
 24
                                                                                     25
 25

    Reinforced concrete pipe (RCP):

                a. American Society for Testing and Materials (ASTM):
                                                                                     26
 26
                     1) C76, Reinforced Concrete Culvert, Storm Drain and
                                                                                     27
 27
                                                                                     28
 28
                         Sewer Pipe.
                         C361, Reinforced Concrete Low-Head Pressure Pipe.
                                                                                     29
 29
                         C443, Joints for Circular Concrete Sewer and Culvert
                                                                                     30
 30
                         Pipe Using Flexible, Watertight, Rubber Gaskets.
                                                                                     31
 31
                    American Water Works Association (AWWA):
                                                                                     32
 32
                         C302, Reinforced Concrete Pressure Pipe, Non-Cylinder
                                                                                     33
 33
                                                                                     34
                         Water and Other Liquids.
 34
                                                                                     35
 35
                                                                                     36
 36
            2. Installation and testing:
                                                                                     37

    a. American Water Works Association (AWWA):

 37
                                                                                     38
                     1) M9, Installation of Concrete Pipe.
 38 -
                                                                                     39
 39
                                                                                     40
 40
            Conduct testing methods to evaluate physical properties of pipe in
            full compliance with ASTM C497 "Determining Physical Properties of
                                                                                     41
 41
            Concrete Pipe or Tile." Report full results test showing
                                                                                     42
 42
                                                                                     43
            compliance with referenced standard.
 43
                                                                                     44
 44
                                                                                     45
 45
            Determine acceptability of RCP in all diameters and classes by
            appropriate ASTM plant tests, including such test to indicate
                                                                                     46
 46
            specified design strengths have been met prior to shipment.
                                                                                     47
 47
                Conduct three-edged bearing test as specified in AASHTO T280,
                                                                                     48
 48
                                                                                     49
                 or by the testing of cores in accordance with AASHTO T24.
 49
                 Complete bearing test prior to shipment date of lot tested.
                                                                                     50
 50
                 Conduct crushing test, as specified on cured concrete
                                                                                     51
 51
                                                                                     52
                 cylinders. Achieve specified 28-day design compressive
 52
                 strength prior to shipment date of lot tested.
                                                                                     53
 53
```

Engineer.

03 !

1-2

01			01
02	PART 3	3 - EXECUTION	02
03			03
04	3.01	INSTALLATION	04
05			05
06	Α.	Observe all recommendations in accordance with AWWA M9 for	06
07	,,,	installation, delivery, and storage of pipe material.	07
08			80
09	3.02	CONNECTIONS WITH EXISTING WORK	09
10			10
11	Α.	All connections made shall be performed in the same manner as the	. 11
		connections of the existing pipes unless otherwise approved by the	, 12
12 13	•	Engineer.	13
14		·	14
15	В.	All existing pipe which has been damaged shall be replaced with	15
16		the same pipe using the same installation method as the existing	16
17		pipe unless otherwise approved by the Engineer.	17
18			18
19			19
20		END OF SECTION	20
21		·	2]



01	SECTION 15103	01
02 03 04	BUTTERFLY VALVES	02 03 04
05 06 07	PART 1 - GENERAL	05 06 07
07 08 09	1.01 SUMMARY	08 09
10 11 12 13	 A. Section Includes: 1. Butterfly valves as included in manholes and distribution box as shown on the plans. 	10 11 12 13
14 15 16 17 18 19 20	 B. Related Sections include but are not necessarily limited to: 1. Division 0 - Bidding Requirements, Contract Forms, and Conditions of the Contract. 2. Division 1 - General Requirements. 3. Section 15060 - Pipe and Pipe Fittings: General. 4. Section 15064 - Pipe: Plastic 	14
21 22	1.02 QUALITY STANDARDS	21 22
23 24 25 26 27 28 29 30 31 32 33 34 35 36	 A. Referenced Standards: American National Standards Institute (ANSI): a. B16.1, Pipe Flanges and Flanged Fittings. American Society for Testing and Materials (ASTM): a. D2241, Specification for PVC Pressure-Rated Pipe. b. D2464, Specification for Threaded PVC Plastic Pipe Fittings, Schedule 80. c. D2466, Specifications for PVC Pipe Fittings, Schedule 40. American Water Works Association (AWWA): a. C504, Rubber Seated Butterfly Valves. Manufacturers Standardization Society of the Valve and Fittings Industry (MSS): a. SP-67, Butterfly Valves. 	23 24 25 26 27 28 29 30 31 32 33 34 35
37 38	1.03 SUBMITTALS	37 38
39 40 41 42 43	 A. Shop Drawings: 1. See Section 01300. 2. For valves 8 IN and larger, furnish "Affidavit of Compliance" with Owner in accordance with AWWA C504. 	39 40 41 42 43
44 45 46	PART 2 - PRODUCTS	44 45 46
47 48	2.01 ACCEPTABLE MANUFACTURERS	47 48
49 50 51 52	 A. Subject to compliance with the Contract Documents, the following Manufacturers are acceptable: 1. ASAHI. 2. Chemtrol. 3. George Fischer 	49 50 51 52

```
01
01
           4. Or approved equal.
                                                                                  02
02
           Submit requests for substitution in accordance with Specification
                                                                                  03
03
                                                                                  04
           Section 01630.
04
                                                                                  05
05
                                                                                  06
    2.02 BUTTERFLY VALVES
06
                                                                                  07
07
                                                                                  08
           Materials:
      Α.
80
                                                                                  09

    Valve bodies:

09
               a. ASTM A126, Class B, or ASTM A536, Grade 65-45-12 ductile
10
                                                                                  11
11
                   Wafer valves may be constructed of ASTM A48, Class 40
                                                                                  12
12
                                                                                  13
                   cast iron.
13
                                                                                  14
           2. Valve shafts:
14
                                                                                  15
               a. Stainless steel, 18-8, Type 403 or 316.
15
                                                                                  16
           3. Valve discs:
16
                                                                                  17
17
                  Potable and nonpotable water:
                                                                                  18
                   1) ASTM A48, Class 40 cast iron.
18
                                                                                  19
                       ASTM A536, Grade 65-45-12 ductile iron.
19
                                                                                  20
                   3) ASTM A436, Type 1 alloy cast iron.
20
                                                                                  21
                       Bronze in accordance with AWWA C504.
21
                                                                                  22
               b. Wastewater and similar applications:
22
                                                                                  23
                   1) ASTM A436, Type 1 alloy cast iron.
23
                   2) ASTM A536, Grade 65-45-12 ductile iron.
                                                                                  24
24
                                                                                  25
                   3) ASTM A436, Type 1 alloy cast iron.
25
                                                                                  26
                   4) Bronze in accordance with AWWA C504.
26
                   Air and similar applications: ASTM A48, Class 40 cast
                                                                                  27
27
                                                                                  28
                    iron:
28
                                                                                  29
               Valve seats and seals:
29
                                                                                  30
                a. Potable and nonpotable water below 150 DegF:
30
                                                                                  31
                    1) Natural rubber.
31
                b. Potable and nonpotable water and wastewater and air below
                                                                                  32
32
                                                                                   33
                    180 DegF:
33
                                                                                  34
                    1) Buna-N.
 34
                                                                                   35
                c. Heating water and air 180 to 250 DegF.
35
                                                                                   36
                    1) EPDM.
 36
                                                                                   37
37
                                                                                   38
        C. Design Requirements:
 38
                                                                                   39
            1. Seat type: Resilient. Comply with AWWA C504.
 39
                                                                                   40
                Exposed and submerged valves 3 through 20 IN.
 40
                    Body type: Wafer or short body flange (laying length
                                                                                   41
 41
                                                                                   42
 42
                    may vary from AWWA C504).
                    Working pressure: Rated for 150 psi (Class 150B per
                                                                                   43
 43
                                                                                   44
                    AWWA C504).
 44
                                                                                   45
                c. Equip wafer type with fully tapped anchor lugs drilled
 45
                                                                                   46
                    per ANSI B16.5.
 46
                                                                                   47
            3. Exposed and submerged valves 24 IN and larger:
 47
                                                                                   48

    a. Body type: Short body flange.

 48
                    Working pressure: Rated for 150 psi (Class 150B per
                                                                                   49
 49
                                                                                   50
                    AWWA C504).
 50
                                                                                   51
            4. Direct buried valves:
 51
                a. All valves: Working pressure rated for 150 psi (Class
                                                                                   52
 52
                                                                                   53
                    150B per AWWA C504).
 53
```

01		01
02		02
03	PART 3 - EXECUTION	03
04		04
05	3.01 INSTALLATION	05
06		06
07	A. Refer to the construction plans for additional information and	07
08	coordination with the HDPE manhole fabrication.	08
09		09
10	B. Comply with the manufacturer's installation guidelines and	10
11	appropriate application recommendations.	. 11
12		. 12
13		13
14	END OF SECTION	14

. .

metals will be affected by use of a rubber or neoprene sheeting,

38 -

28 /

03 1

- F. Coupling Bands: Flexible pipe shall be firmly joined by coupling bands. These bands shall be not more than two nominal sheet thicknesses lighter than the thickness of the pipe to be connected and in no case lighter than 0.052 inches. Unless specified otherwise, the Contractor shall have the option of furnishing any one of the following types of coupling bands.
 - 1. Corrugated bands furnished and installed such that the band corrugations match and conform to the corrugations of the pipe. The gap between the pipe being joined shall be in the center of the band and shall be no wider than one corrugation width. Bands for 12-inch thru 30-inch diameter pipe shall have a minimum width of 12 inches. Bands for pipe with diameters greater than 30 inches shall have a minimum width of 22 inches.
 - Deformed sheet bands (dimple bands) furnished and installed 2. such that the projections match and are of the same depth as the pipe corrugations. These projections shall be formed in circumferential rows with one projection for each corrugation of the helical pipe. Bands for 12-inch diameter pipe shall have a minimum width of 12 inches and shall have one circumferential row of projections for each pipe end being joined. Bands for pipe with diameters greater than 12 inches shall have a minimum width of 24 inches and shall have two circumferential rows of projections for each pipe end being joined. These bands shall be furnished and installed with gasket to provide resistance to infiltration and leakage. The gap between the pipe being joined shall be in the center of the band and shall be no wider than two inches. All bolted connections on coupling bands shall be furnished with cutwashers placed between the nut and the angle bracket, or nuts with integral washers.
- G. Asphaltic or bituminous coatings shall be applied in conformance with manufacturers' requirements and NCDOT Standard Specification, as applicable.

PART 3 - EXECUTION

3.01 GENERAL

- A. Equipment: All equipment necessary and required for the proper construction of culverts shall be on the project, in first class working condition. The Contractor shall provide such mechanical tampers as required to obtain the compaction of the pipe bedding and backfill as specified.
- B. Excavation: The Contractor shall perform all excavation to the depth shown on the plans. The bedding for the pipe shall be so shaped that at least the lower quarter of the pipe shall be in continuous contact with the bottom of the trench. Bedding shall

01		be as shown on the plans.	01
02	c	Placing Pipe: The pipe shall be laid with the separate sections	03
03 04	ι.	joined firmly together with coupling bands with outside laps of	04
05		circumferential joints pointing upgrade, and with longitudinal	Ö!
06		laps on the sides. The pipe shall be laid carefully and true to	06
07		lines and grades on a bed which is uniformly firm throughout	07
08		its entire length. Any pipe which is not in true alignment, or	08
09		which shows any undue settlement after laid or or is damaged,	09
10		shall be taken up and relaid or replaced without extra	_ 10
11		compensation. Pipe shall not be laid on frozen ground.	. 13
12			. 17
13	D.	Connections: Contractor shall follow manufacturer's	13
14		recommendations in installing pipe connections.	10
15			1!
16	Ε.	Backfill: The trench shall be backfilled with material as	10
17		specified in Section 02221.	1
18			13
19		FUD OF DEATION	13
20		END OF SECTION	2
21			

•